APPENDIX E

DRAWINGS AND SPECIFICATIONS

SEDIMENT CONSOLIDATION AREA FINAL DESIGN CAMILLUS, NEW YORK GJ4299.04

D

С



R

Α

LIST OF DRAWINGS

DRAWING NO.	DRAWING TITLE
444853-101-C-001	COVER SHEET
444853-101-C-002	EXISTING SITE CONDITIONS
444853-101-C-003	BERM AND SUBGRADE GRADING PLAN
444853-101-C-004	TOP OF LOW PERMEABILITY SOIL LINER
444853-101-C-005	SUMP GRADING PLAN
444853-101-C-006	TOP OF GRAVEL DRAINAGE LAYER
444853-101-C-007	INSTRUMENTATION AND MONITORING PLAN
444853-101~C~008	POST-SETTLEMENT CROSS SECTIONS
444853-101-C009	LINER SYSTEM DETAILS
444853-101-C-010	LIQUIDS MANAGEMENT SYSTEM DETAILS
444853-101-C-011	INSTRUMENTATION AND MONITORING DETAILS
444853-101-C-012	MISCELLANEOUS DETAILS

444853-

444853-

444853-444853-

444853-

444853

444853

444853

444853-

444853-

444853-



PREPARED BY:

F

Geosyntec[▷] consultants

PARSONS

A A	, В	ė c	b D	ė E	δ F
THE NAME: L-CONDITIONOMINA LAKE-PENNINGSA GEORGESSUSSUED FOR CONSTRUCTION REP-DYRED PLOT DATE: 4/16/2007 12:45 PM PLOTTED BY: FRANK SELL	Ruced set (No Final ConergyRev-2/4280-001 Ding				

- DETAIL NUMBER

DETAIL

,3

SHEET ON WHICH ABOVE DETAIL IS PRESENTED

TITLE OF DETAIL SCALE: 1"=2'





Ŷ	G		Ŷ		Н						
BERM AND SUN	P CONTROL	POINTS	I ¤	<u>DIES.</u>							ĺ
POINT NUMBER	NORTHING	EASTING	Ι.	OBTAINED FROM A	CONTOURS SH TOPOGRAPHIC	MAP COMPL	ed by Ed by	ING WE TVGA	HE_ 161		ĺ
1	1120726	905728		AERIAL PHOTOGRA	NY PERFORME	de irre metr DONI6 APRI Arte nationa	L 2008	A THE	MAP		ĺ
2	1120886	905894		STANDARDS FOR 1	INCH EQUAL 1	to 50 FEET S	CALE.	THE Y PARS	ino.		İ
3	1121250	907092	2.	THE SCA DESIGN S	HOWN ON THIS	DRAWING IS	FOR	CAPA	CITY	1	l
4	1121159	907298	"	OF UP TO 2.65 M	LUON CUBIC Y	ARDS.				l '	
5	1120253	907584	3.	WEIR BOX NO. 6 S CONSTRUCTION PE	hall be aban R The Detail S	doneð befo Shown on d	re b ec Rawing	ENNING 12.			İ
7	1119642	907770	4	THE PERMETER BE	RM SHALL HAV	e a konmun	i heigi	IT OF !	5		ļ
8	1119188	906220		FEET WITH 2.5H: 1V LONGITUDINAL SLO	/ Side Slopes PE of 0.5%	and an ove	RALL N	AENENALIN.	1		ļ
9	1119759	906026	5.	EXCAVATIONS SHA	LE BE PERFORM	ed at Prof	OSED :	SUMP			ĺ
10	1120402	905828		locations per th	e grades pre	Sented on	DRAWN	ig no.	5.	-0	l
11	1120314	906089	6.	The Existing fill Shown on this d	SOLL SHALL BE RAWING PRIOR	to constru	CTING	ihe gr. The	ADES		
12	1120330	906154		PERMILIER BERM L	JURING PHASE	II.	~ ~	• • • •	-		ĺ
13	1120275	906101	ľ.	PER THE GRADES	shown on the	S DRAWING P	RIOPIT	UAWAIC Ö	U U		
15	1120652	907176		REUSED AS DIRECT	ED BY THE EN	GINEER, AN	y Exist Y Exist	ING ID ALS	an er		
16	1120668	907229		REMOVED AND DIS	POSED OF AS I	DIRECTED BY	THE	NCINEE	R,	2	
17	1120629	907241	8.	THE TEMPORARY L	IQUID CONVEYA	NCE CULVER	T SHAL	L CONS	ast St		í
18	1120613	907188		PIPES SHALL BE P	Lugged with E	ENTONITE DE	FORE	alosue	Ē		ł
19	1120583	907541		THEORARY SIRE	ICE WATER COD	utro: straic	TURES	eente	FN		:
20	1120640	907864	۳.	PHASES SHALL BE RUNDN	CONSTRUCTED	TO CONTROL	RUNC	et and	5		Ì
22	1120710	907813	10	TEMPORARY BERM	. Consistent	with detail	5 ON	DRAWN	IG 9		1
23	1120836	907764	~	SHALL BE CONSTR AREA	ucted around	THE DEBRIS	MANA	GEMEN	ſ	[]	
24	1121022	907693		-	LEGF	ND					ł
25	1121181	907634	-	6 70	EXISTING	ground eli	EVATIO	n (fei	T)		r F
26	1121130	907509			(NOTE 1)						i E
27	1121086	907383	-	440	PROPOSED) perimeter	r Beri	a (NO1	(E 4)		
28	1120890	907445	=		EXISTING	road				3	I
30	1120553	905720		WFIR BOX 5	EXISTING	WEIR BOX					l
31	1120455	905648	_	· ·	- PHASE BO	JUNDARY					į
32	1120389	905580	⊢	0		tool	>				
33	1120243	905471		Gt	osyti	llec*					i
34	1120209	905461		1156 000		ltants	1F 200			0	i
35	1120187	905501		1255 KOBE KENN	IESAW, GEORGI PHONE: 678.2	A 30144 US/ 02.9500	12 200				í
36	1120145	905555		1				l			i
38	1120124	905735									
39	1120160	905823									
40	1120243	905794	ź	ADDRESS ADDITIONAL COMMENTS	NYSDEC	APRIL 2011	знs	RK	Æ		i
41	1120392	905764	_	ADTRESS MYSDEC (C	INFINIS	OCT 2010	JHS	RK	.sfi	4	
	[]]]]]		ŀ			00000000	90-00	PA OC	42.		
	11 0) `	<u>1</u>	ISSUED FOR CONSTR	UCIKIN STATE	NF 294	£#₩	17/	3 ₩9	9 ₀ .	i
	10^{-1}		10.	DESCRIPTIK	***		<u>ě</u> ř	°caço	Я÷це	0000	: r
VERIM		\square	JH	S j	141× 2010	ARC -	1	$\mathcal{S}_{\mathcal{S}}$	V		í.
1. S///	KAA	0	CHD DV	1400 ar 1400 ar		K	<u>ا</u>	ľ	18	-10	
S AN A			APP	RONED BY	JULT &UTU	127		₹L		ц. Т.	10.1
HE RO	- T		JF	8 **	JUTY 2010	2	Æ	- - -	د بر د		10
	. 7	Ŋ	9R0	ueet war. R		No S	مشرعت مرجع	33 Ì	ື້		ì
12-2-2-	\neg		F			19	0000	<u> </u>	in,	a.	f
NN D)		PA		18	N	<u>ک</u>	AGAN	5	ŕ
Ann o	all a	1/2		COMMERCI	AL TRCH	NOLDOY	1013	jup.	J		ŀ
	VASTERED	2	000			308 4.4		2	_		
	NWS	-	13	SVI PLAINFIELI SYRACUSE, NY	13212	444	+85.	<u> </u>			i
	1812	0		(315) 451-95	60	-					ł
$ \langle -\rangle$	R	1 C	FRO	JECT TALE							ļ
h > C			L	H	oney	wei				-0	
	122	/	\$	SEDIMENT	CONSO	IDATIO	DN	AR	ΞA		i
	100	1	L	ONOND/	GA LA	KE BO	TTC)M			
	/	1	L	PORPHIE	KEMEL	JAL U	C 21	GN			:
	$\left(\right)$		DRAS	MANCE TITLE							
		6.e.		BERM	AND S		ADE			6	
	~~	+45		GF	ADING	FLAN					
		110									
) altro	(/)	SOA	LE SC. (IFP	ALE: 1" Rented on 2	= 120° 2x34 SHEE	т)				
L-SHI	0 120'	240'	DRA	MAA957	-101	-0-0	07	RE	×. 2		
DY W	SCALE IN	FEET	Ļ	-++000.	101-	00	55		£		ĺ
•	G		0		H						İ
									-		









Ŷ		G			Ŷ		н						
	434 444 ■ WEIR ▲ SB915 ■ PZ ④ SC ■ PZ ● SC	G LEGE EXISTING PROPOS EXISTING BOX 5 EXISTING POX 5 EXISTING POX 5 EXISTING CG4 PROPOS -G7 PROPOS - OP PHASE I PROPOS	ND 3 GROUND ELEVA ed Sca perimet 3 Road 3 Weir Box 5 Piezometer Ed Settlement 5) Boundary Ed Settlement	(NOTE 4) CELL PROFILER	2. 3.	TES. A SURVEY CRID W NUL BE FORTOWNE ROUND. AFTER LATER, A SURVEY LATER, A SURVEY DRAWAGE LATER CONSTRUCTION WE BY LA FTD NOLE ON SURVEY BEFORE CONSTRUCT WHE BY LA FTD SHOLE-WALL CON- SHOL A SURVEY BENCH POPTLER SYSTEM	H ALL BE SET UP ADDR TO CONST DO OBTAN DO STORE DO OBTAN DO STANDAR DO	WITHIN THE I RUCTION. AN INFE ELEVATION. AN INFE ELEVATION CONTINUE REAL RIGHT AND AN INFE INFERENCE INFER	FOOTPRI SINGTAL SINGT TI VEL DRA TAND GR LAYER AND GR SURED ROXIMAT AFTED AFTED G LAYER CED ON CKFRLED THE SET HE SET DOCATION	NT OF L SURV HE EXK WAGE IE LONG 1 R WILL CONG 1 R WILL THE S D WITH FTLEMEIN IELEMEN S OP	THE EY STING 5 FT HE BE AND YI	1	
Nrs	osi-i	ALIGNME G2 PROPOS	init (NOTES 2 A) Ed inclinoretei	NJ 3) RS		NOVED BY TRUCK OF THE WATER IN THE BENCHMARK I	TO EACH LOCA THE TANK SHO EACH THE PRID	tion as nee uld be sur r to the m	DED. T VEYED F EASURE	HE LEV RELATIV	AEL E 10	– °	
PIEZ	OMETE	R CONTROL	POINTS		4.	BEFORE CONSTRUC PEZOMETERS WILL PZ-GI THROUGH I PEZOMETERS WELL AND 45 FT. THE	TION OF THE S DE INSTALLED. P2-67 WITHIN T DE INSTALLED ABOVE PIEZOMIE	CA, VIBRATIN AT PROPOS IHE SCA FOO AT DEPTHS CTERS SHALL IHAN'S SHALL	ig wire Sed Loc Apprint, of 15 f Be Ans	CATIONS THREE 7, 30 TALLED FNT	i of Ft.		
PQIN		NOT LING	Lasung			CASINGS. AT PRO	POSED LOCATIO	NS OF PZ-G	58 AND 1517 Diki	PZ-G9	ON		
P7-	-G2	1120619	907250			PIEZOMETER WELL I INSTALLATION PRO	BE INSTALLED A	T A DEPTH (OF 50 F	FT. TH E WITH	E THE	2	
PZ-	-63	1720087	906781		l I	SPECIFIC MANUFAC	TURER'S INSTRA	JCTIONS.					I
PZ-	G4	1119547	906312		5.	SETTLEMENT CELLS	s will be inista "The sca	ILLED IN THE	GROUN	id befo	ORE		
PZ-	-65	1119899	907476	ł	6.	ALL THE PIEZOMET	ERS AND MOM	NONETERS M	(L 8E #	NSTAL	ED	E	
PZ-	-G6	1120822	905916		[INTRALLY, BUT ON CELLS WILL BE INS	LY PHASE I AND) II PROFILER Y. PHASE I	IS AND II SETTL	SETTLE	WENT		
PZ-	-67	1121175	907078			CELLS AND EXTEND INSTALLED IF CONS	Signs of the F Struction of F	PROFILERS W	el onli Require	r Bec TD,		Ι.	ŀ
PZ-	-68	1121386	905308		7.	INCLINIOMETERS SI	-GI AND SIG2	WILL BE AB	ANDONE	D_USIN	6	r°	1
PZ-	-69	1121105	905645	l	Ľ	APPROPRIATE MET DURING THE CONS	HODS, SUCH AS TRUCTION OF PI	A OVERDRIELIN HASES IN AND	4G, AND) III LINI	BACK	TEMS		ł
NCI	NOME	TER CONTRO		٦	1	AS DERECTED BY T INCLINIOMETER WILL	HE ENGINEER. BE INSTALLED	THE SHAPE IN THE VICK	ACCELAR	RAY (S SI-G3	iaa}		I
					8.	IN THE EVENT OF	INSTRUMENT FA	ILURE BEFOR	EORD	URING			ĺ
POIN	AT ID	Northing	Easting	_		SEDIMENT PLACEM THE GEOTECHINICAL	ENT, REMEDIAL Instrumentat	MEASURES W NON AND MO	rll be Nitorin	taken g Plai	PER I AS		
SI-	-67	1120003	906806			DIRECTED BY THE	ENGINEE, K.					Ι.,	
51-	-62	1120651	906603	_								13	
5	-63	1120108	905835										
51-	-65	1119875	907761		1								
-16	~ 1		1		⊢	~		I	>				
SET	TLEMEN	T CELL CON	TROL POI	NTS		- G	eosyr	itec'	-				1
201		Northing	Fos	lina	1.		consu	iltants					
	C-G1	1120435	906	036		1255 ROB KEN	INTS BORALEVAN	2) N.W. SU A 30144 US 202 9500	A 200			Γ	
	≻-G2	1120254	906	095	⊢	r	rnuNt: 6/8.2	0008.3300					
se	C-63	1120088	906	155		<u> </u>							l
SC	-64	1)19907	905	201				-					
so	-65	1120510	906	325	t.	ADDRESS APRILITATION	L NTSAFC	400-					
so	-G6	1120268	906	401	Ľ	COMMENTS		METRIC 2011	³⁷⁵	NRN .	*5	4	
SC	-67	1120034	906	475 746	h	ADDRESS INSDEC C	COMENTS	homes.	нs	RK	JF8		
SC	ud :-69	1120452	906	/43 759	-		ALA C	NEW		C. S.		ł	
SC	-610	1120712	906	963	Ľ	ISSUED FOR CONST	Beneral L	2010 00 00 00 00 00 00 00 00 00 00 00 00	0	p.			
SC	-GT1	1120471	907	042	NG.		A V SERVICE	<u>F. BE</u>	<mark>е́с</mark> т,	6	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	[ŀ
SC	-612	1120236	907	113	JH	s 🐔	100 2010	T C	Ň	٠Ų,	آ چ	÷	
SC	G13	1120790	907	196	CHE	លេខ ខ្លីំ	ANTE 1]-x	45	1	ы Ш	-0	
SC	~G14	1120611	907	255	RK		SULY 2010	4YA	្ត្រ	- \$	N	1. A.	
SC	-G15	1120449	907	304	J.FI	B S	BILY 2010		€-	ູ ອີ	ģ	÷.	l
SC	-617	1120266	907	266	PRO.	SECT NOR 3	DEC. M	1200	31	¢ζ	Şź		
SC SC	-618	119537	906	316	٦£ ا	B 5	KIRITA 3070	000	**°*	\sim			ŀ
SC	-619	1119374	906	367	$\left[\right]$	EDA.	D ê		NP?		ן ו		ł
SC	-620	1119791	906	548		F A					ĺ	5	ŀ
SC	-621	1119627	906	599	4		IAL TUCH	NULCEY		.P			ŀ
sc	-622	1119464	906	550	0FF	ce 301 PLAINFIEI	D ROAD	^{xe} 44	4853	5			
SC	~G23	1119742	906	961		SYRACUSE, N	13212	•65				Í	ŀ
SC	-624	1119994	907	10/ 237		(515) 451-9	560	<u> </u>					
SC.	-626	119657	907	288	PRO								
sc	-627	1120059	907-	422	ŀ		une)	we					ŀ
SC	-G28	1119889	907-	478	5	SEDIMENT	CONSO	LIDATK	ON	ARE	A		
SC	-629	1119742	907	523		ONOND.	AGA LA			M Chi			l
SC	-630	1120813	905	920	L	2082115	. KEMEL	JAL U	1231	UN			I
SC	-631	1120621	905	#78 203	DRAN	NING TALE							ŀ
50	-633	1120708	306	263	ł	INSTR	UMENTA	TION	ANI)		6	
SC	-G34	1120820	906	533		MON		∍ r'LA	N				ŀ
SC	- G 35	1121094	905	344									l
SC	-636	1120903	906	903	SCAL	r SC	ALE: 1"	= 200	~				
SC	-637	1121166	9070	082	DRAS	(IF" I Minic No.	manu≉EU/ON/2	2x34 SHEE	9	RO	<i>.</i>		ŀ
SC	-638	1120974	907	138		444853	-101-	-C-0	07		2	ŀ	
1		~			1		L.3					J	l
ō		G			ő		н						f















Ŷ	G	Î	H	
		1	NOTES: 1. THE SUMPS, RISER PIPES, AND PUMPS ARE DESIGNED FOR POST-CLOSURE CONDITIONS. ADDITIONAL DEWATERING MEASURES WILL BE IMPLEMENTED DURING OPERATIONS AND CLOSURE AS INFERDED	
		2	2. THE RISER PIPE CAN BE INSTALLED IN VERTICAL SEGMENTS. THE LENGTHS OF RISER PIPE SEGMENTS CAN BE CHANGED BASED ON FIELD CONDITIONS SUCH AS GEOTENIE THEE FILLING SEQUENCE AND ACTUAL DEWAIRSED GEOTEXTLE TUBE HEIGHTS ACHIEVED. EACH SEGMENT SHALL BE PROVIDED WITH LETING LUGS PER MANUFACTURE'S REQUIREMENTS. SEGMENT JOINTS SHALL BE WEIDED TOGETHER IN ACCORDANCE WITH MANUFACTURE'S SPECIFICATIONS. ALTERNATE JOINING WETHODS MAY BE ALLOWED BASED ON APPROVAL BY THE ENDINEER OF RECORD ON A CASE BY CASE BASIS.	1
-		3	3. ELECTRICAL SUBMERSIBLE OR PISTON PUMPS SHALL BE PROVIDED FOR EACH PRIMARY RISER PIPE. PUMP SYSTEM SHALL INCLUE CONTROL PANEL AND NIREE FLOAT SYSTEM WITH INTENSIONLY SAFE RELAY SWITCHES OR ALTERNATE LEVEL CONTROL FEATURES. THE SPECIFIC MODELS SELECTED MUST USE 3-PHASE POWER, PUMP FOR THE WESTERN SUBP SHALL BE CAPABLE OF PUMPING AT A RATE OF 30 CALLONS PER MINUTE (GPM) WITH 50 FEET OF HEAD DURING CLOSURE, PUMP FOR THE EASTEIN SUMP SHALL BE CAPABLE OF PUMPING AT A RATE OF 20 CALLONS PER MINUTE (GPM) WITH 50 FEET OF HEAD DURING CLOSURE, THURF OR THE EASTEIN SUMP SHALL BE CAPABLE OF PUMPING AT A RATE OF 20 CALLONS PER MINUTE (GPM) WITH 50 FEET OF HEAD DURING CLOSURE, THURSE PUMP CAPACITIES CAN BE REDUCED TO 2 CPM AFTER CLOSURE. ALTERNATE PUMP CAPACITIES CAN BE CONSDERED BASE CAP BER REDUCED TO 2 FOR AFTER CLOSURE. ALTERNATE PUMP CAPACITIES CAN BE CONSDERED BASE CAP SREEDCATIONS FOR PARTICULAR PRODUCTS. HIGHER CAPACITIES CAN BE USED DURING OPERATIONS AND CLOSURE AS NEEDED. ACCH PUMP STEM SHALL BE PROVIDED WITH A COUNTER OR EQUIVALENT DEVICE TO REFCORD TOTAL FLOW	ە 2
		4	4. PUMPS NEED NOT BE INSTALLED IN BACKUP RISERS UNDER NORMAL POST-CLOSURE CONDITIONS.	
		5.	5. DETAILS OF THE SUMP, PUMP, CONNECTIONS, AND OTHER COMPONENTS MAY BE CHANGED TO ACCOMMODATE FIELD CONDITIONS AND AVAILABLE PRODUCTS WHILE MAINTAINING THE CENERAL CONCEPTS PRESENTED HEREIN. FOR EXAMPLE, AN ALTERNATE DESIGN WITH A PUMP GUIDE ALONG THE INTEGOR WALL OF THE RISER IS ACCEPTABLE.	0
<u>896</u> 77777	BASE LINER SYSTEM	6.	5. CLEAR WARNING SIGNS SHALL BE PROVIDED FOR EACH RISER STATING THE MAXMUM LIVE LOAD THAT CAN BE APPLIED ON THE COVER. THIS ALLOWADLE LIVE LOAD SHALL BE ADEQUATE TO SUPPORT PUMP REMOVAL BY MAINTENANCE PERSONNEL. 7. SCA SLAPS WILL BE MONITORED FOR THE PRESENCE OF NAPL. PORTABLE PUMPS OR OTHER REMOVAL SYSTEMS WILL BE USED TO REMOVE DETECTED NAPL FROM THE PRIMARY AND RACKING PERSON OF EACH SLAPE. FOR THE PRIMARY AND RACKING PERSON OF EACH SLAPE.	5
		L	NECESSARY.	
ORARY L	ATERAL IPE (SHOWN CLARITY)		CONSULTANCE CONSULTANCE 1255 ROBERTS BOULEVARD, N.W., SUITE 200 1256 ROBERTA JOINT USA	0
)		PHONE: 675.202.9500	1
		2	ADDRESS ADDITIONAL MYSDEC APRIL 2011 JHS RK JE COMMENTS ANDRESS MYSDEC COMMENTS OF CC, 2010 HS MEAN FB	F
		o sc JH Se	SSUED FOR CONSISTENT AND AND AND AND AND AND AND AND AND AND	PREN INT
			B 422 2010 718 20 20 20 5	N.A.A.A.A.A.A.A.A.A.A.A.A.A.A.A.A.A.A.A
				•
		07FIL 0 7 7 7 7 7 7 7 7 7 7 7 7 7	301 PLAINFIELD ROAD SYRACUSE, NY 13212 (315) 451-9560	
		s	Honeywell SEDIMENT CONSOLIDATION AREA ONONDAGA LAKE BOTTOM SUBSITE REMEDIAL DESIGN	0
		DRAW	LIQUIDS MANAGEMENT SYSTEM DETAILS	5
		SCAU	E SCALE: AS SHOWN (IF PRINTED ON 22x34 SHEET)	
		DRAG	444853-101-C-010 2	
0	G	0	H	
			-	





Prepared for

Honeywell 301 Plainfield Road, Suite 330 Syracuse, NY 13212

SPECIFICATIONS

ONONDAGA LAKE SEDIMENT CONSOLIDATION AREA (SCA) FINAL DESIGN SUBMITTAL Camillus, New York

Prepared by



301 Plainfield Road, Suite 350 Syracuse, NY 13212 Geosyntec^D consultants

engineers | scientists | innovators 1255 Roberts Boulevard, Suite 200 Kennesaw, Georgia 30144

Project Number GJ4299

April 2011



PARSONS

SPECIFICATIONS INCLUDED

- 01030 Environmental Protection
- 01620 Health and Safety Requirements
- 02085 Groundwater Monitoring Well Abandonment
- 02100 Site Clearing

UNAUTHORIZED ALTERATION OR ADDITION TO THIS ENGINEERING DOCUMENT IS A VIOLATION OF SEC-TION 7209. PROVISION 2 OF THE NEW YORK STATE EDUCATION LAW.



SPECIFICATION NO:SECTION 01030SPECIFICATION TITLE:ENVIRONMENTAL PROTECTIONPROJECT NO:444853PROJECT TITLE:ONONDAGA LAKE SCA FINAL DESIGNCLIENT:HONEYWELL, INC.

					APPROVAL	S	
Issue	Date	e Pages Issue Description		Prepared	Checked	Approved	
0	12Jul10	11	Original	DDS	LKB	NA	
1	14Oct10	11	Issued with revised 2010 Construction Submittal	DDS	LKB	DDS	
2	21Apr11	Addition of reference to Section 1 11 1.03 and issued with SCA Fina Design Submittal		DDS	LKB	DDS	
Entire Specification Issued this Revision		ion	SPECIFICATION ISSUED FOR:				
Revised Pages Only Issued this Revision		nly ion	In-house ReviewClient Review/ApInformation Only	proval D	Bid Constructio <i>Other</i>	on	

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	2 of 11
Specification Title	Environmental Protection	Date:	21Apr11

SECTION 01030

ENVIRONMENTAL PROTECTION

PART 1 – GENERAL

1.01 **DESCRIPTION**

- A. The Work specified in this Section consists of all labor, equipment, tools, materials, services, supervision and incidentals necessary for environmental pollution control and abatement for the Work as described herein, shown on the Project Drawings, or as directed by the Engineer. Work in this Section includes, but is not limited to controlling environmental pollution requiring the consideration of air, water, and land; management of noise, solid and hazardous waste, and other pollutants.
 - 1. Related Work specified in other Sections includes, but is not limited to:
 - a. Section 02085 Groundwater Monitoring Well Abandonment
 - b. Section 02200 Earthwork

1.02 PERFORMANCE REQUIREMENTS

A. The Contractor shall comply with all applicable Federal, State, and Local codes, ordinances, regulations, statutes and standards.

1.03 REFERENCES

- A. New York State Standards and Specifications for Erosion and Sediment Control, (Latest Version).
- B. New York Department of Transportation: Standard Specifications (US Customary), 2009.
- C. New York State Department of Environmental Conservation: Draft 6 NYCRR Part 375, Environmental Remediation Programs, 2006.
- D. New York State Department of Environmental Conservation: 6 NYCRR Part 360 Regulations.
- E. Resource Conservation and Recovery Act (RCRA)
- F. Toxic Substances Control Act (EPA)

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	3 of 11
Specification Title	Environmental Protection	Date:	21Apr11

1.04 **DEFINITIONS**

- A. Environmental Pollution shall be defined as the presence of chemical, physical, or biological elements or agents which:
 - 1. Adversely affect human health or welfare.
 - 2. Unfavorably alter ecological balances of importance to human life.
 - 3. Affect other species of importance to man.
 - 4. Degrade the utility of the environment for aesthetic and/or recreational purposes.
- B. Prohibited Construction Practices include, but are not limited to the following:
 - 1. For any stream corridor, wetland, surface water or any unspecified location:
 - a. Dumping of spoil material
 - b. Indiscriminate, arbitrary, or capricious operation of equipment
 - c. Pumping of silt-laden water from trenches or other excavations
 - d. Disposal of trees, brush, and other debris
 - 2. Permanent or unspecified alteration of the flow line of any stream.
 - 3. Explosive blasting.
 - 4. Burning of refuse and debris at the project site.

1.05 SUBMITTALS

- A. The Contractor shall submit the following in accordance with Section 01300 Submittal Procedures and as elsewhere specified in this Section:
 - 1. A Contractor's SWPPP with a description of and illustration showing anticipated stormwater control and erosion control measures to be implemented during construction. This shall be submitted prior to mobilization to the Site.
 - 2. Material Safety Data Sheets (MSDS) for all products having MSDSs 10 working days prior to delivery of such product to Site. MSDSs must be maintained and readily available on-site.
 - 3. The Contractor shall be responsible for completing an inspection form for each piece of equipment, tool or bulk recyclable remnant structure or pipe being removed from the Site that required decontamination.
 - 4. An "Off-Site Disposal Record" as part of the Final Closeout Report.

1.06 PROJECT AND SITE CONDITIONS

A. The Contractor shall carefully examine the site to determine the full extent, nature, and location of the Work required to conform to the Contract Drawings and Specifications. The Contractor shall bring any inaccuracies or

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	4 of 11
Specification Title	Environmental Protection	Date:	21Apr11

discrepancies between the Contract Drawings and Specifications to the Engineer's attention in order to clarify the exact nature of the Work to be performed.

PART 2 – PRODUCTS

2.01 DECONTAMINATION PRODUCTS

- A. Cleaning products anticipated for use in decontamination include, but are not limited to the following:
 - 1. A pressure washer (or equivalent) furnished and used by the Contractor shall be a high-pressure, low-volume unit from an industry-recognized manufacturer.
 - 2. The Contractor shall provide miscellaneous tools such as shovels and brushes.
 - 3. The Contractor shall provide cleaning agents such as non-phosphate detergents for use as necessary.

PART 3 – EXECUTION

3.01 **PREPARATION**

- A. Prior to commencement of the Work, the Contractor shall meet with the Engineer to develop mutual understanding relative to compliance with these provisions and administration of the environmental pollution control program.
- B. The Contractor shall schedule and conduct all Work in a manner that will minimize the erosion of soils in the area of the Work and shall provide erosion control measures. All erosion control measures shall be in place and in operating condition in an area prior to any construction activity in that area.
- C. The Contractor shall manage construction water and sequence and conduct earthwork activities to limit the generation of construction water as appropriate.

3.02 TEMPORARY ENVIRONMENTAL CONTROL FEATURES

A. The Contractor will dismantle and remove temporary environmental control features only when permanent control features have been installed and assessed as correctly functioning by the Engineer. Permanent control features shall be incorporated into the Project at the earliest practicable time in light of construction scheduling, and shall be in place and functioning upon project completion.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	5 of 11
Specification Title	Environmental Protection	Date:	21Apr11

3.03 GENERAL REQUIREMENTS

- A. Flow of surface water into excavated areas shall be prevented as much as is practical.
- B. Ditches around construction areas shall also be used to carry non-contact surface storm water away from the excavated areas.
- C. At the completion of the Work, temporary ditches shall be backfilled and the ground surface restored to its original condition.

3.04 **PROTECTION OF STREAMS AND SURFACE WATERS**

- A. The Contractor shall take all precautions to prevent, or reduce to a minimum, any damage to any stream or surface water from pollution by debris, sediment or other material, or from the manipulation of equipment and/or materials in or near such streams or surface water.
- B. The Contractor shall take all preventative measures to avoid spillage of petroleum products and other pollutants. In the event of any spillage, prompt remedial action shall be taken in accordance with all applicable Federal, State and Local codes, ordinances, regulations, statutes and standards and as approved by the Engineer.
- C. Water that has been used for washing or processing, or that contains oils or sediments that will reduce the quality of the water in the stream or surface water shall not be directly returned to the stream or surface water. Such waters shall be diverted to the Temporary Water Treatment Plant or as directed by the Engineer.

3.06 PROTECTION OF LAND RESOURCES

- A. The Contractor shall restore land resources within the project boundaries and outside the limits of permanent Work to conditions upon completion of construction such that these will appear to be natural and not detract from the appearance of the project. Confine all construction activities to areas shown on the Contract Drawings or as approved by the Engineer.
- B. Outside the Limits of Clearing and Grubbing as indicated on the Contract Drawings, the Contractor shall not de-face, injure, destroy, or remove trees, shrubs, fencing, structures, or other landscape features without prior approval by the Engineer. No ropes, cables, or guys shall be fastened to any existing trees, shrubs, fencing, structures or other landscape features for anchorage unless specifically authorized by the Engineer.

PARSONS

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	6 of 11
Specification Title	Environmental Protection	Date:	21Apr11

- C. Prior to operations, the Contractor shall ensure adequate protection for trees, shrubs, fencing, structures or other landscape features that may possibly be defaced, bruised, injured or otherwise damaged by the construction equipment or other operations. Monuments and markers shall be similarly protected.
- D. Any trees, shrubs, fencing, structures or other landscape features scarred or damaged by the Contractor's equipment or operations shall be restored as nearly as possible to their original condition. The Engineer will decide the method of restoration to be used and whether damaged trees shall be treated and healed or removed and disposed of.
- E. The location of the Contractor's support areas shall be approved by the Engineer and shall not be within wetlands or floodplains. The preservation of the landscape shall be an imperative consideration in the selection of support area locations. Drawings showing support area locations shall be submitted for approval of the Engineer.
- F. If the Contractor proposes to construct temporary roads or embankments and excavations for support areas, the following shall be submitted for approval at least 10 days prior to scheduled start of such temporary work:
 - 1. A layout of all temporary roads, excavations, embankments, and drainage to be constructed within the site.
 - 2. Details of temporary road construction.
 - 3. Drawings and cross-sections of proposed embankments and their foundations, including a description of proposed materials.
 - 4. A landscaping drawing showing the proposed restoration of the area. The Drawing must include, but not be limited to the following:
 - a. The proposed removal of any trees, shrubs, fencing, structures, or other landscape features outside the limits of clearing and grubbing.
 - b. The locations of guard posts or barriers required to protect trees, shrubs, fencing, structures or other landscape features to be maintained undamaged.
 - c. The locations of guard posts or barriers required to control vehicular traffic.
 - d. The provision for the obliteration of construction scars and for a natural final appearance of the area.
- G. Modification of the Contractor's approved drawings shall be made only with the written approval of the Engineer. No unauthorized road construction, excavation or embankment construction, including disposal areas will be permitted.
- H. The Contractor shall remove all signs of support areas or any other vestiges of construction as directed by the Engineer. It is anticipated that excavation,

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	7 of 11
Specification Title	Environmental Protection	Date:	21Apr11

filling and plowing of roadways will be required to restore the area to nearnatural conditions in order to allow the growth of vegetation. Roadways will be restored to existing conditions or as directed by the Engineer. The disturbed areas shall be prepared and seeded as approved by the Engineer.

3.07 **PROTECTION OF AIR QUALITY**

A. Dust Control

- 1. The Contractor is responsible for dust control for all excavations, embankments, stockpiles, access roads, plant sites, waste areas, borrow areas and all other work areas.
- 2. An approved method of dust control is sprinkling of water from a water source approved by the Engineer.
- 3. The use of any other stabilization methods may be permitted with approval from the Engineer. Product samples and manufacturer's literature must be submitted to the Engineer in accordance with Section 01300 Submittals and all other relevant Sections contained in the Specifications. All products that are approved for dust control shall be used in accordance with the manufacturer's instructions.
- 4. Sprinkling must be repeated at such intervals as to keep all parts of the disturbed area at least damp at all times, and the Contractor shall have sufficient competent equipment to accomplish this. Dust control shall be performed as the Work proceeds and whenever a dust nuisance or hazard occurs, or as determined by the Engineer.
- B. Odor Control
 - 1. If odors are an issue as determined by the Engineer, the Contractor shall provide an odor control material or applicable procedure acceptable to the Engineer.

3.08 NOISE CONTROL

A. The Contractor shall be aware of all applicable Federal, State, and Local codes, ordinances, regulations, statutes and standards related to noise. The Contractor shall adhere to any local regulations and restrictions regarding the start and stop times of work activities at the site.

3.09 MANAGING WASTE MATERIAL

- A. Managing Waste Material Requirements
 - 1. The Contractor shall manage the handling, segregation, stabilization, containment, storage, loading and transportation of all waste materials resulting from the performance of the Work.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	8 of 11
Specification Title	Environmental Protection	Date:	21Apr11

- 2. All waste storage, staging and loading areas shall be in a location determined by the Engineer.
- 3. Litter, clean construction debris, metal, wood, office trash, etc. or other non-contaminated materials may be disposed of at an approved disposal facility.
- B. Waste Segregation
 - 1. The Contractor shall segregate litter, construction debris, hazardous wastes, and non-hazardous wastes based on generator knowledge.
 - 2. The Contractor shall further segregate non-hazardous wastes (contaminated or uncontaminated) in a similar manner.
 - 3. The Contractor shall keep wastes of unknown classification separate from other wastes and manage as if they were hazardous until a waste determination has been made.
 - 4. If wastes cannot be classified based solely on generator knowledge, the Contractor shall collect waste samples as directed by the Engineer.
- C. Waste Containers
 - 1. The Contractor shall furnish appropriate containers (metal dumpsters with secure lids or covered roll-off containers), for construction debris and/or uncontaminated non-hazardous waste as required.
 - 2. Waste shall be disposed of at frequent and regular intervals as required to prevent the overfilling of such containers. Place non-hazardous solid wastes, construction debris, and litter in containers in accordance with this specification.
 - 3. The Contractor shall visually inspect all containers of wastes for leaks or damage prior to being loaded for transportation and off-site disposal. Transfer contents of any leaking or damaged container to another container or overpacks and re-inspect prior to loading. Clean up, contain, and label spilled materials for disposal in accordance with the Contract Documents.
 - 4. Any material that spills from containers shall be immediately cleaned and placed back into the waste containers.
- D. Waste Transportation and Disposal
 - 1. Dumpsters shall be emptied every two weeks, when full, or as directed by the Engineer. There shall be no liquid allowed in the containers.
 - 2. No waste material shall be buried on-site or used as landfill for any part of grading activities.
 - 3. All Contractor and Subcontract personnel must be trained on correct waste disposal procedures.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	9 of 11
Specification Title	Environmental Protection	Date:	21Apr11

- 4. Honeywell shall agree to the selection of disposal facilities in advance in writing.
- 5. The Contractor shall dispose of waste oils and petroleum products generated during the Work in a safe and environmentally responsible manner.
- 6. A Honeywell Representative will sign all waste profile sheets for waste characterization and manifest(s) for off-site waste disposal of all regulated site generated waste.
- E. Non-Hazardous Wastes
 - 1. The Contractor shall load, transport, and dispose of non-hazardous wastes generated in performance of the Work.
 - 2. Waste containers shall be "sealed" non-leaking dumpsters, or equivalent; maintained to prevent leakage.
 - 3. Before waste containers become full, the Contractor shall dispose of waste off-site.
 - 4. If required, the Contractor shall dispose of non-hazardous wastes at a permitted off-site facility using a permitted waste transporter.
 - 5. A non-hazardous waste manifest or Bill of Lading, signed by Honeywell, shall accompany each waste shipment. The original paperwork, stamped received and signed by the disposal facility, shall subsequently be returned to the Engineer.
 - 6. The Contractor shall furnish all paperwork to the Engineer.
- F. Hazardous & TSCA Waste
 - 1. Honeywell will contract the transportation and disposal (T&D) of all hazardous wastes requiring off-site disposal directly with the T&D facility. Honeywell will decide who will be responsible for waste characterization.
 - 2. Honeywell shall select waste transportation and disposal contractor(s) and issue necessary Purchase Order(s).
 - 3. The Contractor shall:
 - a. Manage hazardous wastes in accordance with RCRA and/or TSCA regulations.
 - b. Place drummed wastes in a lined temporary staging area with berms, aisle space, stacking height, periodic logged inspections, stormwater management, and security in accordance with applicable RCRA regulations for drum management.
 - c. Furnish itemized estimated volumes for Hazardous and TSCA Wastes to be generated by their operations (decontamination waste, used PPE, emergency response waste, etc).
 - d. Place waste materials for off-site disposal in the proper transportation containers, label waste containers, sample and

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	10 of 11
Specification Title	Environmental Protection	Date:	21Apr11

characterize waste, provide temporary storage, prepare waste manifest and coordinate transportation with Honeywell.

- e. Coordinate the management, handling, transport and off-site disposal of hazardous or TSCA regulated wastes resulting from the Work.
- f. Allow seven working days for Honeywell to review and agree to the characterization and manifest documentation prior to scheduling transportation.

3.10 USE OF CHEMICAL PRODUCTS

- A. Chemicals used during project construction or furnished for project operation, whether herbicide, pesticide, disinfectant, polymer, reactant or of other classification, shall be approved by the U.S. EPA or U.S. Department of Agriculture or any other applicable regulatory agency.
- B. The Contractor shall obtain required certifications, permits, and inspections and comply with all Federal, State, Local, and DOT codes, ordinances, regulations, statutes and standards governing transportation, handling, storage, and use of chemical products and residues.
- C. The Contractor shall refer to the pertinent MSDS for information on all chemical products used or present at the Site.

3.11 FUEL AND LUBRICANTS

- A. The Contractor shall comply with all applicable Federal, State, and Local codes, ordinances, regulations, statutes and standards concerning transportation and storage of fuels and lubricants.
- B. Fuel storage area and fuel equipment shall be approved by the Engineer prior to installation.
- C. The Contractor shall report spills or leaks from fueling equipment or construction equipment to the Engineer and cleanup as required.
- D. The Engineer will require the Contractor to remove damaged or leaking equipment from Project site.

3.12 DECONTAMINATION

- A. The Contractor shall properly decontaminate all tools and equipment before removal from site.
- B. The Contractor shall properly decontaminate all supplies and materials before removal from site, or manage as waste materials in accordance with the requirements of this specification.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01030	Page:	11 of 11
Specification Title	Environmental Protection	Date:	21Apr11

- C. The Contractor shall use decontamination pads in order to separate exclusion and clean zones as required as follows:
 - 1. The decontamination pad shall be used and maintained to accommodate the anticipated construction equipment at the approved location. The area shall be returned to its previous condition upon completion of the Work unless otherwise directed by the Engineer.
 - 2. When not in use, each decontamination pad shall be covered with a waterproof liner to prevent the collection of precipitation.
 - 3. Wood planks may be placed over the impermeable liner at the Contractor's discretion to provide a traveling surface for vehicle wheels and equipment tracks.
 - 4. All decontamination water collected in the decontamination pad shall be managed as construction water.
 - 5. All equipment and material decontamination procedures shall be carried out on the decontamination pad.
 - 6. The collection sump shall be purged at the end of each work day and as required, and/or following a rainfall event.

[END OF SECTION]

SPECIFICATION NO:SECTION 01620SPECIFICATION TITLE:HEALTH AND SAFETY REQUIREMENTSPROJECT NO:444853PROJECT TITLE:ONONDAGA LAKE SCA FINAL DESIGNCLIENT:HONEYWELL, INC.

					APPROVAL	S
Issue	Date	Pages	Issue Description	Prepared	Checked	Approved
0	12Jul10	3	Original	DDS	LKB	NA
1	14Oct10	3	Issued with Revised 2010 Construction Submittal	DDS	LKB	DDS
2	21Apr11	3	Issued with SCA Final Design Submittal	DDS	LKB	DDS
Entire Specification Issued this Revision			SPECIFICATION ISSUED FOR:			
Revised Pages Only Issued this Revision		nly ion	In-house ReviewClient Review/ApInformation Only	proval 🛛	Bid Constructio	on

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01620	Page:	2 of 3
Specification Title	Health and Safety Requirements	Date:	21Apr11

SECTION 01620

HEALTH AND SAFETY REQUIREMENTS

PART 1 – GENERAL

1.01 DESCRIPTION

A. This Section shall communicate the minimum Safety, Health and Emergency Response requirements for performing field activities necessary for completion of the Work as described herein, as shown on the Project Drawings, or as directed by the Engineer.

1.02 PERFORMANCE REQUIREMENTS

- A. The Contractor shall comply with all applicable Federal, State, and Local codes, ordinances, regulations, statutes and standards.
- B. The Contractor shall plan for, and ensure that, all personnel comply with the basic provisions of OSHA General Construction Standards (29 CFR 1926), and any applicable local, state, and federal regulations related to worker health and safety.
- C. The Contractor shall plan for, and ensure that, all personnel directly involved in waste excavation, trenching operations, or other intrusive work shall meet applicable requirements of OSHA Hazardous Waste Operations and Emergency Response, Final Rule (29 CFR 1910).
- D. The Contractor shall ensure that all project training, documentation and work conforms to their Contractor's Health and Safety Plan.

1.03 REFERENCES

- A. *Title 29 Code of Federal Regulations, Part 1910 Occupational Safety and Health Standards* US Department of Labor, OSHA.
- B. *Title 29 Code of Federal Regulations, Part 1926 Safety and Health Regulations for Construction* US Department of Labor, OSHA.

1.04 SUBMITTALS

- A. The Contractor shall submit the following in accordance with Section 01300 Submittal Procedures and as elsewhere specified in this Section:
 - 1. The Contractor Health and Safety Plan (HASP).

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 01620	Page:	3 of 3
Specification Title	Health and Safety Requirements	Date:	21Apr11

1.05 PROJECT AND SITE CONDITIONS

A. The Contractor shall carefully examine the site to determine the full extent, nature, and location of work required to conform to the Contract Drawings and Specifications. The Contractor shall bring any inaccuracies or discrepancies between the Contract Drawings and Specifications to the Engineer's attention in order to clarify the exact nature of the Work to be performed.

PART 2 – PRODUCTS (NOT APPLICABLE)

PART 3 – EXECUTION

3.01 HEALTH AND SAFETY PLAN

- A. The Contractor shall prepare a site-specific health and safety plan (HASP). The Contractor is solely responsible for adequacy of the HASP's preparation, monitoring, management, and enforcement. The Contractor's HASP shall reference the Parsons 2007 SHARP (Safety, Health, and Risk Program) Management, and shall address, but not be limited to, the following:
 - 1. Hazard evaluation
 - 2. On-site safety responsibilities
 - 3. Work zones
 - 4. Drum Removal
 - 5. Personnel training
 - 6. Personal protection, clothing, and equipment
 - 7. Medical Surveillance
 - 8. Emergency procedures
 - 9. Equipment Maintenance and Cleaning
 - 10. Material Safety Data Sheets (MSDS)
 - 11. Noise and Dust Management
 - 12. Fall Protection
 - 13. Confined Space Entry
 - 14. Crane Safety
 - 15. Hot Work
 - 16. Utility Clearance
 - 17. Hazardous Energy Control
 - 18. Excavations
 - 19. Scaffolds and Ladders
- B. The HASP shall be submitted prior to the start of work for approval by the Engineer. Any delay in work due to lack of approved HASP shall be the responsibility of the Contractor.

[END OF SECTION]

SPECIFICATION NO: SECTION 02085

SPECIFICATION TITLE: GROUNDWATER MONITORING WELL ABANDONMENT

PROJECT NO: 444853

PROJECT TITLE: ONONDAGA LAKE SCA FINAL DESIGN

CLIENT: HONEYWELL, INC.

				APPROVALS		
Issue	Date	Pages	Issue Description	Prepared	Checked	Approved
0	12Jul10	10	Original	DDS	LKB	NA
1	14Oct10	10	Schedule A was modified.	DDS	LKB	DDS
2	21Apr11	10	Issued with SCA Final Design Submittal	DDS	LKB	DDS
Entire Specification Issued this Revision		tion sion	SPECIFICATION ISSUED FOR:			
Revised Pages Only Issued this Revision		Only sion	In-house Review Client Review/Ap Information Only	BidoprovalConstructionyOther		

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02085	Page:	2 of 10
Specification Title	Groundwater Monitoring Well Abandonment	Date:	21Apr11

SECTION 02085

GROUNDWATER MONITORING WELL ABANDONMENT

PART 1 – GENERAL

1.01 DESCRIPTION

- A. The Work specified in this Section consists of all labor, equipment, tools, materials, services, supervision, and incidentals necessary to perform abandonment of existing groundwater monitoring wells and piezometers as necessary for completion of the Work as described herein, shown on the Project Drawings, or as directed by the Engineer. Work in this Section includes, but is not limited to:
 - 1. Abandonment of existing groundwater monitoring wells and piezometers as noted in Schedule A.
- B. Related Work specified in other Sections includes, but is not limited to:
 - 1. Section 02200 Earthwork

1.02 PERFORMANCE REQUIREMENTS

A. The Contractor shall comply with all applicable Federal, State, and Local codes, ordinances, regulations, statutes and standards.

1.03 REFERENCES

- A. American Society for Testing and Materials (ASTM)
 - 1. ASTM C150 Standard Specification for Portland Cement.
 - 2. ASTM D5299 Guide for the Decommissioning of Groundwater Wells, Vadose Zone Monitoring Devices, Boreholes, and Other Devices for Environmental Activities.
- B. New York State Department of Environmental Conservation (NYSDEC) CP-43: "Ground Water Monitoring Well Decommissioning Policy", November 2009.

1.04 SUBMITTALS

A. The Contractor shall submit the following in accordance with Section 01300 – Submittal Procedures and as elsewhere specified in this Section:

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02085	Page:	3 of 10
Specification Title	Groundwater Monitoring Well Abandonment	Date:	21Apr11

- 1. The proposed methods of abandonment including drilling and grouting as required. The Contractor shall be responsible for the adequacy and safety of the methods.
- 2. Mixes Grout mixes, bentonite mixture.
- 3. Equipment Drill rig and related equipment.
- 4. Drilling Contractor Name and address of the proposed well driller and a list of at least five completed projects of similar construction.
- 5. Piezometer/Well Field Inspection Log (Attachment A).
- 6. Piezometer/Well Decommissioning Record (Attachment B).

1.05 PROJECT AND SITE CONDITIONS

A. The Contractor shall carefully examine the site to determine the full extent, nature, and location of work required to conform to the Contract Drawings and Specifications. The Contractor shall bring any inaccuracies or discrepancies between the Contract Drawings and Specifications to the Engineer's attention in order to clarify the exact nature of the Work to be performed.

PART 2 – PRODUCTS

2.01 MATERIAL

- A. Grout
 - 1. Provide a standard Portland Cement/bentonite grout mixture consisting of Portland Cement (ASTM C150 Type I), bentonite, and water in the proportions of one 94-pound bag of Type I Portland Cement, 3.9 pounds of powdered bentonite, and 7.8 gallons of potable water. Slightly more water may be used in order to penetrate a sand pack when a screen transects multiple flow zones. This mixture results in a grout with a bentonite content of four percent by weight and will be used in all cases except in boreholes where excessive use of grout is anticipated. In these cases refer to NYSDEC CP-43, Section 6.2.
- B. Bentonite
 - 1. Provide ¹/₂-inch diameter sodium bentonite pellets or equal.
 - 2. Baroid Ben Seal or equal.

2.02 EQUIPMENT

A. The Contractor shall use equipment suitable for well abandonment activities.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02085	Page:	4 of 10
Specification Title	Groundwater Monitoring Well Abandonment	Date:	21Apr11

PART 3 – EXECUTION

3.01 **PREPARATION**

- A. No abandonment activities shall commence without the prior approval of the Engineer.
- B. Perform abandonment in accordance with the requirements of this Section.
- C. Review available information concerning each well and piezometer to be abandoned, including well construction diagrams and abandonment summary table (Schedule A), prior to commencement of work.
- D. Complete the Well Field Inspection Log (Attachment A) prior to work.

3.02 ABANDONMENT

- A. The following refers to all monitoring wells and piezometers that are singlecased and do not penetrate into bedrock. All shall be abandoned by one of the following methods:
 - 1. Grouting In-Place.
 - 2. Grouting In-Place Followed by Casing Pulling.
 - 3. Overdrilling and Grouting With or Without a Temporary Casing.
- B Refer to Schedule A for the selection method for abandonment of each monitoring well.
- C. Methods
 - 1. Grouting In-Place
 - a. For the purposes of these procedures, the well-seal is defined as the bentonite seal above the sand pack.
 - b. If the well-seal is not compromised and there is no confining layer present, grouting in-place is considered a satisfactory abandonment procedure.
 - c. If the seal is compromised, Method 2 may be necessary.
 - d. Grouting in-Place Procedure
 - i. Do not remove the outer protective casing until grouting is complete.
 - ii. Using a tremie, pump the well casing and screen with grout according to the procedures in Section 6.4 of NYSDEC CP-43.
 - iii. The outer protective steel casing should be removed from either a fifteen foot depth or below the frostline, whichever is greater.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02085	Page:	5 of 10
Specification Title	Groundwater Monitoring Well Abandonment	Date:	21Apr11

- iv. Cut the well casing at a minimum fifteen foot depth and remove it and any associated well materials.
- v. The upper fifteen feet of casing and the outer protective casing may be removed in one operation if a casing-cutter is used.
- 2. Grouting In-Place Followed by Casing Pulling
 - a. This method of abandonment is to be used when the well assembly must be removed to clear the site.
 - b. The well construction and depth must be such that pulling will not break the riser.
 - c. This method is acceptable only when:
 - i. No contamination is present; or
 - ii. If contamination is present, the well does not penetrate or cross a confining layer.
 - d. If contamination is likely to cross a penetrating layer during pulling, a temporary casing may be used (See 4. Overdrilling and Grouting With or Without a Temporary Casing).
 - e. Casing Pulling Procedure:
 - i. If the protective steel casing shall interfere with the down-hole work, it may be removed in a manner that minimizes disturbance to the well casing and surrounding ground.
 - ii. Lower a drill rod down the well and perforate the bottom wellcap.
 - iii. Grout as per Section 6.4 of NYSDEC CP-43.
 - iv. Pull the well by grappling the casing with appropriate devices and pulling the casing and well materials as a single unit.
 - v. Additional grout must be used as the well casing and screen are withdrawn to ensure that the void spaces are adequately filled.
 - vi. If the well is highly contaminated, is installed in a collapsible formation or if the bottom well-cap cannot be punctured, the casing or screen must be perforated prior to pulling.
 - vii. If all of the well materials are not withdrawn during the pulling process, overdrilling of the remaining portions may be required as directed by the Engineer.
- 3. Overdrilling and Grouting With or Without a Temporary Casing
 - a. This technique will remove an entire well, its sandpack, and old grout column.
 - b. This technique is to be used where the assembly is expected to sever or break or the well penetrates a confining layer, and the well materials must be removed.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02085	Page:	6 of 10
Specification Title	Groundwater Monitoring Well Abandonment	Date:	21Apr11

- c. A temporary casing may be required prior to drilling, pulling, and grouting.
- d. The Overdrilling Method should follow the original well borehole, be at least the diameter of the original well borehole, and advance at least 0.5 foot beyond the original well borehole depth.
- e. The Overdrilling Method should remove all construction materials.
- f. In order to keep the augers centered on the original well borehole, fill the well column with grout after perforating the bottom well-cap, prior to proceeding with overdrilling while the grout is not yet dry.
- g. If required by Schedule A, the Contractor shall submit a method for overdrilling based on site conditions for approval by the Engineer.
- h. Refer to Section 2.4 of NYSDEC CP-43 for further details of techniques for the Overdrilling Method.

3.03 COMPLETION

- A. Dispose of well and piezometer materials and associated soil cuttings in a temporary lined and covered stockpile on Wastebed 13 (exact location to be determined by the Engineer). Removed and abandoned well materials (i.e. well casings, screens, steel casings, and etc.) shall be cut into 10 foot or shorter sections prior to disposal.
- B. Upon completion of grouting, ensure that the final grout level is approximately five feet below land surface. Embed a ferrous metal marker in the top of the grout to indicate the location of the former well. Place a fabric "utility" marking one foot above the grout.
- C. Restore the area in the vicinity of each well location as shown on the Contract Drawings or as directed by the Engineer.
- D. Complete the Well Decommissioning Record (Attachment B) following completion of the Work.
- E. Following drilling activities, decontaminate equipment in accordance with the decontamination protocol in Section 01030 Environmental Protection.

[END OF SECTION]

SCHEDULE A

Location ID Instrument Type/ Abandonment Method		Location ID	Instrument Type/ Abandonment Method
SB915-PZ13-01S	ON HOLD	SB915-PZ-A2I	VW/Overdrill & Grout
SB915-PZ13-01D	ON HOLD	SB915-PZ-A2D	VW/Overdrill & Grout
SB915-PZ13-01N	ON HOLD	SB915-PZ-A3S	VW/Overdrill & Grout
SB915-PZ13-02I	VW/Overdrill & Grout	SB915-PZ-A3I	VW/Overdrill & Grout
SB915-PZ13-02D	VW/Overdrill & Grout	SB915-PZ-A3N	VW/Overdrill & Grout
SB915-PZ13-02N	VW/Overdrill & Grout	SB915-PZ-A4S	VW/Overdrill & Grout
SB915-PZ13-03S	VW/Overdrill & Grout	SB915-PZ-A4I	VW/Overdrill & Grout
SB915-PZ13-03I	VW/Overdrill & Grout	SB915-PZ-A4D	VW/Overdrill & Grout
SB915-PZ13-03D	VW/Overdrill & Grout	SB915-PZ-A5S	VW/Overdrill & Grout
SB915-PZ13-04S	VW/Overdrill & Grout	SB915-PZ-A5I	VW/Overdrill & Grout
SB915-PZ13-04I	VW/Overdrill & Grout	SB915-PZ-A5D	VW/Overdrill & Grout
SB915-PZ13-04D	VW/Overdrill & Grout	SB915-PZ-A6S	VW/Overdrill & Grout
SB915-PZ13-04N	SP/GIP & Overdrill top 15 ft	SB915-PZ-A6I	VW/Overdrill & Grout
PZ-01I	SP/GIP & Overdrill top 15 ft	SB915-PZ-A6D	VW/Overdrill & Grout
PZ-01D	SP/GIP & Overdrill top 15 ft	SB915-PZ-A7S	SP/Overdrill & Grout
PZ-02S	SP/Overdrill & Grout	SB915-PZ-A8I	VW/Overdrill & Grout
PZ-02I	SP/GIP & Overdrill top 15 ft	SB915-PZ-A9S	VW/Overdrill & Grout
PZ-02D	SP/GIP & Overdrill top 15 ft	SB915-PZ-A10D	VW/Overdrill & Grout
PZ-02N	SP/GIP & Overdrill top 15 ft	SB915-PZ-A11I	VW/Overdrill & Grout
BA-01S	SP/Overdrill & Grout	SB915-PZ-A12D	SP/GIP & Overdrill top 15 ft
BA-02S	SP/Overdrill & Grout	SB915-INEX-A1	INCL/GIP & Overdrill top 15 ft
BA-03S	SP/Overdrill & Grout	SB915-INEX-A2	INCL/GIP & Overdrill top 15 ft
--------------	----------------------	----------------	-----------------------------------
SB915-PZ-A1S	VW/Overdrill & Grout	SB915-INEX-A7	INCL/GIP & Overdrill top 15 ft
SB915-PZ-A1I	VW/Overdrill & Grout	SB915-INEX-A8	INCL/GIP & Overdrill top 15 ft
SB915-PZ-A1N	VW/Overdrill & Grout	SB915-INEX-A10	INCL/GIP & Overdrill top 15 ft
SB915-PZ-A2S	SP/Overdrill & Grout	SB915-INEX-A13	INCL/GIP & Overdrill top 15 ft
P2-01S	SP/Overdrill & Grout	P3-01S	SP/Overdrill & Grout
P1-01S	SP/Overdrill & Grout	P1-02S	SP/Overdrill & Grout

Notes:

- 1. SP indicates standpipe piezometer.
- 2. VW indicates vibrating wire piezometer.
- 3. INCL indicates inclinometer.
- 4. GIP indicates grout in-place.

ATTACHMENT A

FIELD INSPECTION LOG

DATE/TIME:		
	PZ/WELL ID:	<u></u>
	YES	NO
WELL VISIBLE? (If not, provide directions below)		
WELL I.D. VISIBLE?		
WELL LOCATION MATCH SITE MAP? (if not, sketch actual location on back)		1
WELL I.D. AS IT APPEARS ON PROTECTIVE CASING OR WELL:		
	YES	NO
SURFACE SEAL PRESENT?		
SURFACE SEAL COMPETENT? (If cracked, heaved etc., describe below)		<u> </u>
PROTECTIVE CASING IN GOOD CONDITION? (If damaged, describe below)		<u> </u>
HEADSPACE READING (ppm) AND INSTRUMENT USED		
TYPE OF PROTECTIVE CASING AND HEIGHT OF STICKUP IN FEET (If applicable)		
PROTECTIVE CASING MATERIAL TYPE:		
MEASURE PROTECTIVE CASING-INSIDE DIAMETER (inches):		
	YES	NO
LOCK PRESENT?		
LOCK FUNCTIONAL?	······	
DID YOU REPLACE THE LOCK?		
IS THERE EVIDENCE THAT THE WELL IS DOUBLE CASED? (If yes, describe below)		. <u> </u>
WELL MEASURING POINT VISIBLE?	·····	
MEASURE WELL DEPTH FROM MEASURING POINT (Feet):		· · · · · · · · · · · · · · · · · · ·
MEASURE DEPTH TO WATER FROM MEASURING POINT (Feet):		
MEASURE WELL DIAMETER (Inches):		
WELL CASING MATERIAL:		
PHYSICAL CONDITION OF VISIBLE WELL CASING:		
ATTACH ID MARKER (if well ID is confirmed) and IDENTIFY MARKER TYPE		
PROXIMITY TO UNDERGROUND OR OVERHEAD UTILITIES		
DESCRIBE ACCESS TO WELL: (Include accessibility to truck mounted rig, natural obstrue	tions, overhead	
	ACK IE NECESSARY	

DESCRIBE WELL SETTING (For example, located in a field, in a playground, on pavement, in a garden, etc.) AND ASSESS THE TYPE OF RESTORATION REQUIRED.

E g more and

IDENTIFY ANY NEARBY POTENTIAL SOURCES OF CONTAMINATION, IF PRESENT

(e.g. Gas station, salt pile, etc.):

REMARKS:

ATTACHMENT B

WELL DECOMMISSIONING RECORD

Site Name:	Well I.D.:	
Site Location:	Driller:	
Drilling Co.:	Inspector:	
0	Date:	

DECOMMISSIONING DATA		WELL SCHEMATIC*		
(Fill in all that app	(Fill in all that apply)			
		(feet)		
OVERDRILLING				
Interval Drilled				
Drilling Method(s)				
Borehole Dia. (in.)				
Temporary Casing Installed? (y/n)				
Depth temporary casing installed				
Casing type/dia. (in.)				
Method of installing				
-				
CASING PULLING	1			
Method employed				
Casing retrieved (feet)				
Casing type/dia. (in)				
	<u></u>			
CASING PERFORATING				
Equipment used				
Number of perforations/foot				
Size of perforations				
Interval perforated				
GROUTING				
Interval grouted (FBLS)]
# of batches prepared			_	
For each batch record:				
Quantity of water used (gal.)				
Quantity of cement used (lbs.)				
Cement type				
Quantity of bentonite used (lbs.)			_	
Quantity of calcium chloride used (lbs.)				
Volume of grout prepared (gal.)			_	
Volume of grout used (gal.)		I		
COMMENTS:		* Sketch in si	If relevant decommissioning	e data, meluding:
		interval ove	adtilled, interval grouted, ca	using left in hole.
		well stickup	s. eic.	
L.,		·		

Drilling Contractor

.

Engineer

SPECIFICATION NO:SECTION 02100SPECIFICATION TITLE:SITE CLEARINGPROJECT NO:444853PROJECT TITLE:ONONDAGA LAKE SCA FINAL DESIGN

CLIENT: HONEYWELL, INC.

					APPROVAL	S
Issue	Date	Pages	Issue Description	Prepared	Checked	Approved
0	12Jul10	4	Original	DDS	LKB	NA
1	14Oct10	4	Issued with Revised 2010 Construction Submittal	DDS	LKB	DDS
2	21Apr11	4	Issued with SCA Final Design Submittal	DDS	LKB	DDS
Entire Specification Issued this Revision		tion sion	SPECIFICATION ISSUED FOR:			
Revised Pages Only Issued this Revision)nly sion	In-house Review Client Review/Ap Information Only	oproval D	Bid Construct <i>Other</i>	ion

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02100	Page:	2 of 4
Specification Title	Site Clearing	Date:	21Apr11

SECTION 02100

SITE CLEARING

PART 1 – GENERAL

1.01 SCOPE OF WORK

- A. The Work specified in this Section consists of all labor, equipment, tools, materials, services, supervision and incidentals necessary to remove and dispose of debris, brush, trees, vegetation, topsoil, and other objectionable materials from Work areas as described herein, shown on the Contract Drawings, or as directed by the Engineer. Work in this Section includes, but is not limited to:
 - 1. Clearing to limits shown on the Contract Drawings;
 - 2. Clearing to establish access routes, support areas, and other work areas as shown on the Contract Drawings, as necessary to complete the Work, or as directed by the Engineer;
 - 3. Protection and preservation of trees and vegetation outside the Limits of Clearing; and
 - 4. Cutting, chipping, and on-site use or disposal of above-grade timber and brush.

1.02 RELATED WORK

- A. Work in this section includes, but is not limited to:
 - 1. Section 01030 Environmental Protection
 - 2. Section 01300 Submittal Procedures
 - 3. Section 01620 Health and Safety Requirements
 - 4. Section 02200 Earthwork

1.03 PERFORMANCE REQUIREMENTS

A. The Contractor shall comply with all applicable Federal, State, and Local codes, ordinances, regulations, statutes and standards.

1.04 SUBMITTALS

- A. The Contractor shall submit the following in accordance with Section 01300 Submittal Procedures and as elsewhere specified in this Section:
 - 1. The Limits of Clearing; and

PARSONS

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02100	Page:	3 of 4
Specification Title	Site Clearing	Date:	21Apr11

2. The proposed methods for managing debris, brush, trees, stumps, vegetation, and other debris.

1.05 **PROJECT AND SITE CONDITIONS**

A. The Contractor shall carefully examine the site to determine the full extent, nature, and location of work required to conform to the Contract Drawings and Specifications. The Contractor shall bring any inaccuracies or discrepancies between the Contract Drawings and Specifications to the Engineer's attention in order to clarify the exact nature of the Work to be performed.

PART 2 – PRODUCTS (NOT APPLICABLE)

PART 3 – EXECUTION

3.01 SITE CLEARING

- A. Provide erosion control measures prior to and throughout all clearing activities.
- B. Limit clearing activities to the Limits of Disturbance shown on the Contract Drawings, or as otherwise approved by the Engineer.
- C. Manage construction water and sequence clearing activities to limit the generation of construction water as appropriate.
- D. Remove all vegetation within the limits of excavation and limits of disturbance, including, but not limited to brush, trees, shrubs, stumps, logs, debris, and boulders. Dispose of all removed material on the areas of Wastebed (WB) 13 not designated for SCA or other facility construction.
- E. Immediately restore or replace any damaged items.
- F. Provide a chipper and/or grinder of sufficient size to handle material expected from the cleared areas and chip/grind cleared vegetation.
- G. Do not burn on or off-site.
- H. Remove or abandon by overdrilling and grouting all existing instrumentation within the limits of the SCA footprint of Wastebed 13, including, but not limited to historic wells, settlement plates, inclinometers, and piezometers. All removed materials shall be disposed of as directed by the Engineer.

PARSONS

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02100	Page:	4 of 4
Specification Title	Site Clearing	Date:	21Apr11

3.02 GUARANTEE

A. The Contractor shall guarantee that Work performed under this Section will not permanently damage trees, shrubs, turf or plants designated to remain, or other adjacent work or facilities. If damage resulting from operations appears during a period up to 12 months after completion of the project, the Contractor must replace damaged items.

[END OF SECTION]



SPECIFICATIONS INCLUDED

- 02200 Earthwork
- 02250 Low Permeability Soil Layer
- 02300 Gravel Drainage Layer
- 02710 Geotextile Cushion
- 02772 Geosynthetic Clay Liner
- 02740 Geomembrane Liner



SPECIFICATION NO: SECTION 02200

SPECIFICATION TITLE: EARTHWORK

PROJECT NO: 444853

PROJECT TITLE: ONONDAGA LAKE SCA FINAL DESIGN

CLIENT: HONEYWELL, INC.

					APPROVAI	LS
Issue	Date	Pages	Issue Description	Prepared	Checked	Approved
0	12Jul10	9	Original	JMS	RK	
1	13Oct10	11	 Issued for Construction Revisions to Section 1.05E; 2.01B; 3.09C, and 3.09D. Added cover page and updated headers. 	JMS	RK	JFB
2	21Apr11	11	Response to Comments Revisions to Sections 1.03A, 1.05A, and 2.01C.	RK	JFB	JFB
Ei Is:	ntire Specifica sued this Revi evised Pages C sued this Revi	tion sion Only sion	SPECIFICATION ISSUED FOR:	oproval	☐ Bid ⊠ Construc	tion

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	2 of 11
Specification Title	Earthwork	Date:	21 April 11

SECTION 02200

EARTHWORK

PART 1 – GENERAL

1.01 SCOPE OF WORK

- A. Furnish all labor, materials, equipment, supervision, and incidentals necessary to perform all excavation, backfilling, and grading necessary for completion of the work shown on the Drawings and as specified herein. The work shall include, but is not necessarily limited to: site preparation, dewatering, excavation, relocating, screening, stockpiling, preparing and/or hauling soils for proper disposal offsite or reuse onsite, subgrade preparation and grading, provision of imported fills, placement and compaction of engineered fill, survey control associated with earthworks, appurtenant work completed in accordance with the Drawings and Specifications, and all related work, as directed by the Engineer.
- B. All soil fill placed as a part of this project, including the perimeter berms, shall be considered as engineered fill and shall be placed, tested, and documented in accordance with the requirement of this Section unless specifically approved by the Engineer.
- C. The low permeable soil liner and gravel drainage layer are not considered engineered fill.
- D. All excavation, trenching, sheeting, bracing, etc. shall comply with the requirements of OSHA excavation safety standards (29 CFR PART 1926.650 Subpart P).

1.02 RELATED WORK

- A. Work in this section includes, but is not limited to:
 - 1. Section 01030 Environmental Protection
 - 2. Section 01300 Submittal Procedures
 - 3. Section 01620 Health and Safety Requirements
 - 4. Section 02100 Site Clearing
 - 5. Section 02250 Low Permeability Soil Layer

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	3 of 11
Specification Title	Earthwork	Date:	21 April 11

1.03 REFERENCES

- A. Latest version of American Society for Testing and Materials (ASTM) Standards:
 - 1. ASTM D 422 Standard Test Method for Particle Size Analysis of Soils.
 - 2. ASTM D 698 Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft3 (600 kN-m/m3)).
 - 3. ASTM D 1556 Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method.
 - 4. ASTM D 2216 Standard Test Methods for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass.
 - 5. ASTM D 2487 Standard Test Method for Classification of Soils for Engineering Purposes (Unified Soil Classification System).
 - 6. ASTM D 2937 Standard Test Method for Density of Soil in Place by the Drive-Cylinder Method.
 - 7. ASTM D 4318 Standard Test Method for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
 - 8. ASTM D 2974 Standard Test Method for Moisture, Ash, and Organic Matter of Peat and Other Organic Soils.
 - 9. ASTM D 6938 Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)
 - 10. ASTM C 136 Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.

1.04 SUBMITTALS

- A. The Contractor shall submit the following information to Engineer for review and approval in accordance with Section 01300 Submittal Procedures and as elsewhere specified in this Section 30 calendar days prior to initiating earthwork activities:
 - 1. List of equipment proposed for the earthwork;
 - 2. Proposed offsite borrow source(s);
 - 3. Dewatering methods and techniques;
 - 4. Dust control equipment and procedures;
 - 5. Methods for supporting trenches, backfilling, compaction, grading, and stormwater control;
 - 6. Coordination of survey requirements for the earthwork;
 - 7. Locations of on-site temporary soil stockpile areas;

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	4 of 11
Specification Title	Earthwork	Date:	21 April 11

- 8. Coordination of earthwork activities with surface-water management and erosion and sediment control measures;
- 9. Schedule for earthwork activities; and
- 10. Quality Control Work Plan.
- B. The Contractor shall be responsible for the adequacy and safety of the methods.
- C. Test results as specified herein shall be submitted to the Engineer for review within two (2) working days of receipt of results. The Contractor shall not deliver material to the site prior to submission and approval by the Engineer of the geotechnical and analytical chemistry test results.

1.05 CONSTRUCTION QUALITY CONTROL

- A. The Contractor shall submit a Quality Control (QC) Workplan for review to the Engineer. Once instituted, the Contractor shall use the QC Workplan to ensure that the Work performed under the contract meets the requirements of the Contract Documents.
- B. The Contractor shall submit the name of a qualified Independent Testing Laboratory (ITL) to the Engineer for review.
 - 1. The Contractor shall submit to the Engineer for approval, the company name, address, and qualifications of the selected ITL proposed for use at the project. Included in this submittal will be the names and qualifications of the individuals who are proposed for assignment to the site. The Engineer reserves the right to request other information regarding the qualifications of the ITL for use in the evaluation process.
- C. Sampling
 - 1. The Contractor shall be responsible for collecting samples and conducting tests using a qualified ITL to document material property compliance with the specifications.
 - 2. The Contractor shall be responsible for collecting samples and conducting tests using a qualified ITL to certify and document that imported material meets the allowable analytical compound concentrations and properties specified in this Section. These samples will be collected and transported in compliance with the QC Workplan. The Engineer reserves the right to observe sampling and testing of the materials. The Contractor shall provide at least 24-hours notice of a sampling event to the Engineer.
 - 3. Representative samples of each specific material type from each specific material source will be obtained by compositing at least five randomly selected individual samples of approximately equal weight. The total composite sample mass shall be at least the minimum size required to

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	5 of 11
Specification Title	Earthwork	Date:	21 April 11

conduct all of the required material property and analytical chemistry tests for that material type. Each of the individual samples will be obtained from within the boundaries of the material mass that the composite sample represents. In addition, at least one (1) pound of each individual sample will be retained in a separate, sealed clean glass jar for mercury testing and for additional duplicate testing, if needed.

- 4. Contractor quality control samples may be obtained from in situ samples for pre-approval of a dedicated borrow source area. The sampling methodology and means for assuring the material dedication to the project shall be submitted to the Engineer for approval prior to the commencement of sampling.
- 5. Contractor quality control samples may also be obtained from dedicated stockpiles or storage/transportation vessels. The sampling methodology and means for assuring the material dedication to the project shall be submitted to the Engineer for approval prior to the commencement of sampling.
- D. Sample Frequency
 - 1. A representative composite sample will be obtained from each 2,500 cubic yards or part thereof with a minimum of 1 sample from each borrow source area with consistent appearance.
- E. Analytical Chemistry Testing
 - 1. These samples will be sent to an Analytical Chemistry Testing Laboratory (ACTL) selected by the Engineer. Each composite sample for each material shall be tested for the compounds in Table 375-6.8(b) "Restricted Use Soil Cleanup Objectives" in NYSDEC Subpart 375. All test results shall be below the Commercial cleanup objective concentrations provided in this table, with exceptions as allowed by NYSDEC, but in no case greater than Industrial Standards. Failure of a single compound test result shall mean that the entire material batch will be rejected unless specifically accepted on a test-by-test basis in writing by the Engineer.
- F. Material Property Testing
 - 1. Each composite sample shall be tested for material properties as defined in the specific specification section or sub-section for that material type.
- G. General
 - 1. No imported materials shall be delivered to the project site before the required material property and analytical chemistry testing for that batch has been provided to the Engineer and written approval received from the

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	6 of 11
Specification Title	Earthwork	Date:	21 April 11

Engineer. Unapproved material shall be removed from the site at the Contractor's expense.

2. Contractor shall be responsible for repairing or reconstructing the deficiencies at his own expense to meet this specification and other Contract Documents.

1.06 CONSTRUCTION QUALITY ASSURANCE

- A. The Engineer shall conduct quality assurance sampling on materials delivered to the site.
 - 1. The Contractor shall provide access and support to the delivered materials in order for representative sampling and testing to be conducted.
 - 2. The Engineer shall have the right to visit the borrow source at any time during borrow pit working hours to observe mining, manufacturing, stockpiling or loading operations.

1.07 AS-BUILT DOCUMENTATION

- A. The Contractor shall provide clearly marked-up set of contract drawings showing all field changes, additions, deletions, and/or corrections.
- B. In addition to preparation of as-built revisions to the Project Drawings, the Contractor shall provide as-built documentation for the top surface of placed engineered fill.

PART 2 – PRODUCTS

2.01 MATERIALS

- A. Engineered fill is defined as placed and compacted soil, as required herein, to achieve grade elevations.
- B. Soil materials used for engineered fill shall consist of relatively homogeneous natural soils free of materials, which, due to nature or size, are deleterious to the intended use. Unless otherwise specified herein, engineered fill shall classify as SC, SM, ML, CL, GM, GC, or GW according to the Unified Soil Classification System (per ASTM D 2487) or combinations of these materials. Classification shall be based on the results of soil conformance tests.
- C. The Contractor shall perform the following material property tests, prior to material being delivered to the site, at the frequency specified in Section 1.05:
 - 1. Grain size (ASTM D 422 or ASTM C 136)
 - 2. Moisture (ASTM D 2216)
 - 3. Standard Proctor (ASTM D 1556)

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	7 of 11
Specification Title	Earthwork	Date:	21 April 11

- 4. Atterberg Limits (ASTM D 4318)
- 5. Organic Content (ASTM D 2974)
- D. These control tests will be performed at each visual or textural change in source material, or as directed by the Engineer. Test results shall be submitted to the Engineer in accordance with Part 1.04.

2.02 EQUIPMENT

A. Contractor shall furnish equipment to perform the scope of work described in this specification, including excavation, hauling, placement, spreading, and compacting engineered fill.

PART 3 – EXECUTION

3.01 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Material not immediately used as engineered fill shall be stockpiled in areas approved by Engineer.
- B. Stockpiled material shall be managed in accordance with the Contractor's procedures approved by Engineer.

3.02 SITE PREPARATION

- A. Contractor shall coordinate the work such that required inspections and testing of work that will be covered up by the placement of engineered fill will be complete prior to placement of the engineered fill.
- B. The Contractor shall construct staging and stockpile areas in approved areas if needed.
- C. The Contractor shall construct temporary haul roads and drainage structures as required for the Contractor to access the staging areas and soil stockpiles.
- D. Locate monitoring wells, piezometers, utilities, and other subsurface structures in the work area. Protect and maintain or abandon these structures and utilities during the excavation and grading activities in accordance with the notes on the Project Drawings.
- E. Prior to earthwork activity, the Contractor shall perform clearing and preparation of work areas in accordance with Section 02100 Site Clearing.
- F. Prior to the start of construction, notify the appropriate organizations and have underground utilities staked or marked. Utilities include, but are not limited to water, gas, electric, telephone, cable, storm sewer, sanitary sewers, laterals, and

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	8 of 11
Specification Title	Earthwork	Date:	21 April 11

services. If utility locations indicate a possible interference, or points of connection to existing facilities need to be identified, perform exploratory excavations to determine the utility's location and elevation. Provide the utility owner with results from exploratory excavations for review. Allow the Engineer sufficient time to review exploratory excavation results and evaluate if changes are required to the Contract Documents prior to the start of construction.

3.03 SUMP EXCAVATION

- A. Sump excavation shall be performed to achieve the grades shown on the Project Drawings. Appropriate excavation protection measures shall be taken to protect the stability of the excavation and safety of workers.
- B. Sump excavation shall be carried out during the presence of the Engineer. Sump excavation schedule shall be closely coordinated with the Engineer and subsequent liner construction activities to minimize the time the excavation remains open. Temporary backfill may be used as an interim excavation protection measure if it is not feasible to complete the liner system construction in the sump area and install the risers and backfill with the drainage layer gravel within a reasonable period of time.
- C. Material excavated from the sump area shall be placed in an area of Wastebed 13, as directed by the Engineer and rough graded to blend into the surrounding topography. If excavated material is placed outside of the area for SCA operations, the area shall be stabilized after placement by vegetation with a seed mix that shall be approved by the Engineer.

3.04 ABANDONING WEIR BOX

A. One of the three existing weir boxes at the site shall be abandoned in accordance with the Project Drawings and as directed by the Engineer. Weir box abandoning shall be carried out during the presence of the Engineer.

3.05 INSTRUMENTATION

A. The Contractor shall excavate instrumentation trenches and backfill them as presented on the Project Drawings and as directed by the Engineer.

3.06 DUST CONTROL

A. Contractor shall provide and operate necessary equipment and personnel to maintain dust control during construction. Contractor is responsible for establishing the means and methods for dust control.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	9 of 11
Specification Title	Earthwork	Date:	21 April 11

B. Contractor shall implement dust control measures during periods of site construction activities. Areas to receive dust control measures include active work areas, site access roads, and other areas of the site with activities that may generate dust.

3.07 STOCKPILING

- A. The Contractor shall stockpile soils as needed in areas approved by Engineer.
- B. The Contractor shall construct stockpiles no steeper than 3-horizontal to 1-vertical (3H:1V) grade to drain and seal by tracking perpendicular to the slope contours with a bulldozer and dress daily during periods when fill is taken from the stockpile. Stock piles shall not exceed a height of 10 feet without prior approval on a case by case basis by the Engineer.
- C. The Contractor shall stabilize stockpiles that will remain out of active use for a period greater than 6 months by vegetation with a seed mix that shall be approved by the Engineer.

3.08 SITE GRADING

- A. Perform earthworks to the lines and grades as shown on the Project Drawings.
- B. In work areas where water ponding is observed, implement measures to remove the water.

3.09 ENGINEERED FILL

- A. Use engineering fill material that meets the material requirements of this Section. Place engineered fill material to the limits and grades shown on the Project Drawings.
- B. Place engineered fill material on surfaces that are free of debris, branches, mud or other deleterious materials.
- C. Place fill material in loose lifts with a thickness of $8" \pm 2"$. In areas where compaction is to be performed using hand-operated equipment, place the fill material in loose lifts with a thickness of $4" \pm 1"$. The first lift shall be placed with a loose lift thickness of up to $24" \pm 2"$. If 24" lifts are not adequate to bridge the soft subgrade, the Contractor shall propose alternate methods, to be approved by the Engineer, for achieving compaction requirements on subsequent lifts (e.g., placement of a nonwoven geotextile [minimum 8 oz./yd²] or other geotextile demonstrated to be suitable).

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	10 of 11
Specification Title	Earthwork	Date:	21 April 11

- D. Remove visible rock particles such that adequate compaction can be achieved. As a guide, rock particles with a nominal dimension larger than 4" for $8" \pm 2"$ thick loose lifts and 2" for $4" \pm 1$ " should be removed.
- E. Prior to placing a succeeding lift of fill material over a previously compacted lift or the prepared subgrade, thoroughly scarify the previous lift to a depth of 2" by discing, raking, or tracking with a dozer. Moisture condition the preceding lift if the moisture content is not within the range of acceptable moisture contents specified in this Section.
- F. Fill slopes steeper than three horizontal to one vertical shall be constructed by overfilling beyond the planned finished fill surface and cutting the slope back to expose properly compacted engineered fill.
- G. Trafficking of scarified surfaces by trucks or other equipment, with rubber tires is not permitted.
- H. The maximum acceptable soil clod size is 3". Reduce clod size by discing, raking, tracking with a dozer, using a soil stabilizer, or other approved means.
- I. Engineered fill shall be compacted to a minimum dry density of 95 percent of the maximum dry density, and -2 to 2 percent of the optimum moisture content as measured using ASTM D 698. The first lift is not subjected to this compaction requirement.
- J. Moisture condition the fill material to achieve the compaction requirements of this Section. Use a water spraying system for wetting. During wetting or drying, regularly disc, rake, or otherwise mix the material to thoroughly blend the moisture throughout the lift. Use discing, raking, or other appropriate methods to dry the material as required.
- K. Replace and rework materials that become unsuitable or unstable as a result of work during inclement weather.
- L. Rework or remove and replace engineered fill that does not meet the compaction requirements of this Section.

3.10 SURVEY CONTROL

A. Survey the limits and elevations of completed prepared subgrade and top of finished fill surface. The thickness of layers shall be verified to be within specified tolerances prior to placement of overlying layers. Thickness verification may be by survey, or by the placement of marker rods or posts on the top of the completed lift indicating the maximum lift thickness before

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02200	Page:	11 of 11
Specification Title	Earthwork	Date:	21 April 11

placement of the loose soil materials, or by excavation of potholes to measure loose lift thickness following placement and before compaction.

B. Provide As-Built drawings that include all field changes, additions, deletions, and/or corrections clearly marked.

3.11 TOLERANCES

A. Construct the finished surface of engineered fill and excavations slopes to a tolerance of +0.2% of the slopes indicated on the Project Drawings when measured at any point along a 50 feet straight-edge. These tolerances shall not result in slopes that are less than the minimum slopes required on the Project Drawings.

[END OF SECTION]

SPECIFICATION NO: SECTION 02250

SPECIFICATION TITLE: LOW PERMEABILITY SOIL LAYER

PROJECT NO: 444853

PROJECT TITLE: ONONDAGA LAKE SCA FINAL DESIGN

CLIENT: HONEYWELL, INC.

					APPROVAI	_S
[ssue	Date	Pages	Issue Description	Prepared	Checked	Approved
0	12Jul10	14	Original	JMS	RK	
1	13Oct10	14	Issued for ConstructionAdded cover page and updated headers.	JMS	RK	JFB
2	21Apr11	14	 Response to Comments Page 9, Section 3.03B. Additional requirement added. Page 9, Item 3.03C. Reference changed to Section 3.10. 	JMS	RK	JFB
Entire Specification Issued this Revision		tion sion	SPECIFICATION ISSUED FOR:			
Revised Pages Only Issued this Revision		only sion	In-house Review Client Review/Ap Information Only	oproval D	BidConstrucOther	tion

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	2 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

SECTION 02250

LOW PERMEABILITY SOIL LAYER

PART 1 – GENERAL

1.01 SCOPE OF WORK

- A. The work covered in this Section consists of the placement of a Low Permeability Soil Layer as part of the base liner system for the Sediment Consolidation Area (SCA) over the existing Solvay Waste in Wastebed 13. This layer shall be placed on prepared subgrade in accordance with the Project Specifications and Drawings. The Contractor shall furnish all labor, materials, equipment, supervision, and incidentals necessary to perform the scope of work.
- B. The Low Permeability Soil Layer is to be constructed out of uniform material to a minimum 12" thickness (minimum 18" in sump areas). The top six (6) inches of the Low Permeability Soil Layer shall have a hydraulic conductivity of no more than 1×10^{-6} cm/sec.

1.02 RELATED WORK

- A. Work in this section includes, but is not limited to:
 - 1. Section 01030 Environmental Protection
 - 2. Section 01300 Submittal Procedures
 - 3. Section 01620 Health and Safety Requirements
 - 4. Section 02100 Site Clearing
 - 5. Section 02200 Earthwork

1.03 REFERENCES

- A. Latest version of American Society for Testing and Materials (ASTM) Standards:
 - 1. ASTM D 422 Standard Test Method for Particle-Size Analysis of Soils.
 - 2. ASTM D 698 Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³ (600kN-m/m³)).
 - 3. ASTM D 1557 Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN-m/m³))
 - 4. ASTM D 1556 Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	3 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

5.	ASTM D 2216	Standard Test Methods for Laboratory Determination of
		Water (Moisture) Content of Soil and Rock by Mass
6.	ASTM D 2487	Standard Practice for Classification of Soils for
		Engineering Purposes (Unified Soil Classification
		System).
7.	ASTM D 2937	Standard Test Method for Density of Soil in Place by
		the Drive-Cylinder Method
8.	ASTM D 4318	Standard Test Method for Liquid Limit, Plastic Limit,
		and Plasticity Index of Soils.
9.	ASTM D 5084	Standard Test Method for Measurement of Hydraulic
		Conductivity of Saturated Porous Materials Using a
		Flexible Wall Permeameter.
10.	ASTM D 5321	Standard Test Method for Determining the Coefficient
		of Soil and Geosynthetic or Geosynthetic and
		Geosynthetic Friction by the Direct Shear Method.
11.	ASTM D 2974	Standard Test Method for Moisture, Ash, and Organic
		Matter of Peat and Other Organic Soils.
12.	ASTM D 6938	Standard Test Method for In-Place Density and Water
		Content of Soil and Soil-Aggregate by Nuclear
		Methods (Shallow Depth).

1.04 SUBMITTALS

- A. The Contractor shall submit the following information to Engineer for review and approval in accordance with Section 01300 – Submittal Procedures and as elsewhere specified in this Section 30 calendar days prior to initiating Low Permeability Soil Layer activities.
 - 1. Mechanical mixing procedure and equipment to uniformly blend the borrow source soil used for the Low Permeability Soil Layer if needed;
 - 2. Equipment and methods for management of various stockpiles, including moisture conditioning and stabilization of stockpiles. Management of stockpiles shall also include methods to measure and monitor material stockpiles;
 - 3. Equipment and methods to load and haul processed material from the material stockpiles if needed;
 - 4. Equipment and methods to scarify, place, spread, and moisture condition Low Permeability Soil Layer material;
 - 5. Repair procedure for Low Permeability Soil Layer;
 - 6. Proposed offsite borrow source(s);
 - 7. Coordination of survey requirements for the earthwork;
 - 8. Locations of on-site temporary soil stockpile areas;
 - 9. Coordination of construction activities with surface-water management and erosion and sediment control measures;

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	4 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

- 10. Schedule for construction activities; and
- 11. Quality Control Work Plan.

The Contractor shall be responsible for the adequacy and safety of the methods.

B. Test results as specified herein shall be submitted to the Engineer for review within two (2) working days of receipt of results. The Contractor shall not deliver material to the site prior to submission and approval by the Engineer of the geotechnical and analytical chemistry test results.

1.05 CONSTRUCTION QUALITY CONTROL

- A. The Contractor shall submit a Quality Control (QC) Workplan for review. Once instituted, the Contractor shall use the QC Workplan to ensure that the Work performed under the contract meets the requirements of the Contract Documents.
- B. The Contractor shall submit the name of a qualified Independent Testing Laboratory (ITL) to the Engineer for review.
 - 1. The Contractor shall submit to the Engineer for approval, the company name, address, and qualifications of the selected ITL proposed for use at the project. Included in this submittal will be the names and qualifications of the individuals who are proposed for assignment to the site. The Engineer reserves the right to request other information regarding the qualifications of the ITL for use in the evaluation process.
- C. Sampling
 - 1. The Contractor shall be responsible for collecting samples and conducting tests using a qualified ITL to document material property compliance with the specifications.
 - 2. Representative samples of each specific material type from each specific material source will be obtained by compositing at least five randomly selected individual samples of approximately equal weight. The total composite sample mass shall be at least the minimum size required to conduct all of the required material property tests for that material type. Each of the individual samples will be obtained from within the boundaries of the material mass that the composite sample represents.
 - 3. Contractor quality control samples may be obtained from in situ samples for pre-approval of a dedicated borrow source area. The sampling methodology and means for assuring the material dedication to the project shall be submitted to the Engineer for approval prior to the commencement of sampling.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	5 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

- 4. Contractor quality control samples may also be obtained from dedicated stockpiles or storage/transportation vessels. The sampling methodology and means for assuring the material dedication to the project shall be submitted to the Engineer for approval prior to the commencement of sampling.
- D. Minimum Sample Frequency
 - 1. QC testing per Part 360 will require a representative sample obtained and tested at the following frequencies (with a minimum of 1 sample from each borrow source area with consistent appearance):

One soil particle size analysis, organic content, and soil classification for every 2,500 cubic yards of Low Permeability Soil Layer material placed; one moisture content and Atterberg Limit analysis of plastic and liquid limit and plasticity index for every 1,000 cubic yards of Low Permeability Soil Layer material placed; one laboratory permeability test using triaxial cell with back pressure for every 5,000 cubic yards of Low Permeability Soil Layer material placed; and one comparison of the moisture-densitypermeability relation for every 5,000 cubic yards of soil liner material placed.

- 2. QA Testing frequency per Part 360 will include density and moisture content tests to be performed at a minimum of nine locations per acre per lift of Low Permeability Soil Layer material placed and one Shelby tube sample for laboratory permeability testing per acre (top 6" lift only). Any tests resulting in penetration of the Low Permeability Soil Layer will be repaired as required in 3.05 of this specification.
- E. Material Property Testing
 - 1. Each composite sample shall be tested for material properties as defined in the section 2.01.E.
- F. General
 - 1. No imported materials shall be delivered to the project site before the required material property testing for that batch has been provided to the Engineer and written approval received from the Engineer. Unapproved material shall be removed from the site at the Contractor's expense.
 - 2. Contractor shall be responsible for repairing or reconstructing the deficiencies at his own expense to meet this specification and other Contract Documents.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	6 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

1.06 CONSTRUCTION QUALITY ASSURANCE

- A. The Engineer shall conduct quality assurance sampling and field compaction testing on Low Permeability Soil Layer materials.
 - 1. The Contactor shall provide access and support for the sampling and testing.
 - 2. The Engineer shall have the right to visit the borrow source at any time during borrow pit working hours to observe mining, manufacturing, stockpiling or loading operations.

PART 2 – PRODUCTS

2.01 MATERIALS

- A. Material for the Low Permeability Soil Layer shall be obtained from off-site borrow areas. The borrow sources and blending and processing procedures, as needed, will be established in accordance with this Section. The Contractor shall not add any additives to meet the hydraulic conductivity requirements of this Section without performing additional laboratory testing of a sample of amended soil as required by the Engineer and subject to approval by the Government Agencies. Segregate and stockpile non-conforming soils, as needed. Process only those materials as needed and identified through preconformance testing as meeting the material requirements of this Section.
- B. Soils not meeting the requirements of this Section shall be considered for use for other construction in accordance with the requirements of Section 02200-Earthwork.
- C. Low Permeability Soil Layer material shall meet the following requirements:
 - 1. Meet the following particle size requirements (ASTM D 422):
 - a. the Low Permeability Soil Layer shall have 100 percent of the particles having a maximum dimension not greater than one (1) inch;
 - b. the Low Permeability Soil Layer shall have not less than 50 percent of the particles, by weight, passing through the standard U.S. No. 200 standard sieve; and
 - c. the Low Permeability Soil Layer shall classify as SC, SM, ML, or CL according to the Unified Soil Classification System (per ASTM D 2487) or combinations of these materials.
 - 2. The Low Permeability Soil Layer material shall have a hydraulic conductivity not more than 1×10^{-6} cm/s when tested in the laboratory in accordance with ASTM D 5084 at a confining pressure of 3000 psf and a hydraulic gradient less the 30.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	7 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

- D. The Low Permeability Soil Layer material shall meet the minimum required peak and residual internal/interface friction angles when tested as a layered sandwich representing the liner system of the SCA (low permeability soil, geomembrane, geotextile, and gravel drainage layer) in accordance with ASTM D 5321.
- E. The Contractor shall perform the following tests before and during construction at the frequency specified in Section 1.05:
 - 1. Grain size (ASTM D 422)
 - 2. Moisture Content (ASTM D 2216)
 - 3. Atterberg Limits (ASTM D 4318)
 - 4. Organic Content (ASTM D 2974)
 - 5. Unified Soil Classification (ASTM D 2487)
 - 6. Hydraulic Conductivity (ASTM D 5084)
 - 7. Standard Proctor (ASTM D 698)
- F. The Contractor shall perform a minimum of one round of the following tests per borrow source, prior to material being delivered to the site:
 - 1. Interface Direct Shear (ASTM D 5321)
 - Certification and test results certifying that the material meets Table 375-6.8(b) "Restricted Use Soil Cleanup Objectives" in NYSDEC Subpart 375. All test results shall be below the Commercial cleanup objective concentrations provided in this table.
- G. These control tests will be performed at each visual or textural change in source material, or as directed by the Engineer. Test results shall be submitted to the Engineer in accordance with Part 1.04.
- H. Construction water for moisture conditioning Low Permeability Soil Layer material shall be obtained from an on-site water source approved by the Engineer.

2.02 EQUIPMENT

- A. The Contractor shall provide equipment required to obtain soil samples for preconformance testing, process, stockpile, and load soil for the borrow area and stockpile as specified in this Section and indicated on the Project Drawings.
- B. The Contractor shall provide equipment to haul and place Low Permeability Soil Layer material in uniform loose lift thicknesses as specified in this Section.
- C. The Contractor shall provide tank trucks, hoses, sprinklers, soil stabilizers, or other equipment designated to apply water uniformly and in controlled

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	8 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

quantities to moisture condition Low Permeability Soil Layer material and to reduce drying to soil surfaces.

- D. The Contactor shall provide equipment to compact soil lifts to the moisture content, dry density, and hydraulic conductivities specified in this Section.
- E. The Contractor shall provide grading equipment to achieve uniform layers, sections, and smoothness of grade for compaction and drainage.

PART 3 – EXECUTION

3.01 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. The soil stockpile area shall be managed as approved by the Engineer.

3.02 LOW PERMEABILITY SOIL LAYER PERFORMANCE CRITERIA

- A. The Low Permeability Soil Layer is to be constructed out of uniform material to a minimum 12" thickness (minimum 18" in sump areas). The top six (6) inches of the Low Permeability Soil Layer shall have a hydraulic conductivity of no more than 1 x 10⁻⁶ cm/sec and shall be compacted to a minimum dry density of 95 percent of the maximum dry density and -3 to 3 percent of the optimum moisture content, as measured using ASTM D 698. All other parts of the Low Permeability Soil Layer shall be compacted to a minimum dry density of 90 percent of the maximum dry density, and -3 to 3 percent of the optimum moisture content as measured using ASTM D 698. The first lift shall not be subjected to the above requirements.
- B. The Low Permeability Soil Layer material shall meet the minimum required peak and residual internal/interface friction angles when tested as a layered sandwich representing the liner system of the SCA (low permeability soil, geomembrane, geotextile, and gravel drainage layer) in accordance with ASTM D 5321.
- C. If conformance tests indicate that any portion of the compacted Low Permeability Soil does not meet the requirements of this Section, the Engineer shall delineate the extent of the non-conforming area. The Contractor shall rework the non-conforming area until acceptable test results are obtained.

3.03 MATERIAL PLACEMENT

A. The Contractor shall place the Low Permeability Soil Layer material only after completion of conformance testing and written confirmation of acceptance of Low Permeability Soil Layer material by the Engineer.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	9 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

- B. Prior to placement of Low Permeability Soil Layer material, clear the surface on which the Low Permeability Soil Layer material is to be placed so that the surface is free of debris, mud and other deleterious material. Any vegetation that inhibits the placement of the Low Permeability Soil layer shall be removed. The Engineer shall inspect and approve that the subgrade is acceptable prior to placement of the Low Permeability Soil Layer material.
- C. Prepare surface of underlying subgrade and survey in accordance with Section 3.10 of Earthwork specification 02200 prior to scarification.
- D. Construct Low Permeability Soil Layer to the minimum thicknesses and slopes shown on the Project Drawings. The thickness of the Low Permeability Soil Layer at any location shall be perpendicular to the plane of the slope at that location.
- E. Remove visible rock particles with a maximum dimension larger than one (1) inch for the Low Permeability Soil Layer material during placement, spreading, stabilizing, compaction, grading, and sealing. Place rock particles removed from the Low Permeability Soil Layer material in a stockpile in an area approved by the Engineer.
- F. In areas where compaction is to be performed, place the Low Permeability Soil Layer material in loose lifts with a thickness of $8" \pm 2"$. In areas where compaction is to be performed using hand-operated equipment, place the Low Permeability Soil Layer material in loose lifts with a loose lift thickness of $4" \pm 1"$. Loose lift thicknesses shall be measured after spreading. The first lift shall be placed with a loose lift thickness of $12" \pm 2"$.
- G. Do not place a succeeding lift of Low Permeability Soil Layer material over any area until the performance testing by the Engineer of the compacted lift in the area is approved and complete.
- H. Prior to compacting a succeeding lift of material over a previous lift, scarify the previous lift to a depth of 2". Moisture condition the succeeding lift in accordance with this Section. Scarify each preceding lift prior to placing the next lift by using a disc, tracking back and forth with a bulldozer, or a combination of both.
- I. Limit the trafficking of scarified surfaces by trucks or other equipment, except stabilizer, moisture conditioning, and compaction equipment.
- J. Moisture condition the loose lift of Low Permeability Soil Layer material prior to compaction if necessary. Distribute the moisture through the loose lift using soil stabilizer or other approved equipment. Moisture condition, if necessary, as follows:

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	10 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

- 1. If the Low Permeability Soil Layer material is drier than required, process the material using the procedure established in this Section to obtain a uniform consistency, distribute water uniformly into the soil to achieve the required moisture content, and then process the material again to obtain uniform mixing. The Contractor shall check the moisture content of the soil at the completion of these three steps and/or after compaction. Repeat the latter two steps if the measured moisture content is not within the acceptable range specified in this Section.
- 2. If the Low Permeability Soil Layer material is wetter than required, dry the material by processing using the procedure established in this Section. The Contractor shall check the moisture content of the soil at the completion of processing or compaction. Repeat the processing if the measured moisture content is not within the acceptable range specified in this Section.
- 3. After moisture conditioning, remove visible rock particles with a maximum dimension larger than one (1) inch for the Low Permeability Soil Layer.
- K. Prepare the last lift of the layer to meet the minimum thicknesses and slopes indicated on the Project Drawings. Meet the construction tolerance requirements specified in this Section.

3.04 MATERIAL COMPACTION

- A. Compact loose lifts using appropriate number of passes, and equipment, and equipment overlap to achieve the performance criteria specified in this Section.
- B. Maintain surface of Low Permeability Soil Layer material in moist condition to avoid crusting and desiccation. In the event crusting and desiccation occurs, protect the compacted Low Permeability Soil Layer in accordance with this Section.
- C. Prepare the finished compacted Low Permeability Soil Layer surface to be acceptable for placement of the geomembrane layer.

3.05 **PERFORATIONS**

- A. Backfill perforations in the Low Permeability Soil Layer resulting from survey stakes or other activities as specified in this Section. Perforations resulting from drive cylinder density tests shall be filled by the Contractor.
- B. Prepare soil-calcium bentonite mix for use in backfilling of perforations as specified in this Section. The mix shall consist of a minimum of 10 percent by weight calcium bentonite granules mixed with Low Permeability Soil Layer material by dry weight basis.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	11 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

- C. Backfill perforations with soil-calcium bentonite mix. Place soil-calcium bentonite mix in perforations in approximately 3" thick loose lifts and rod tamp to compact.
- D. Perforations in the compacted Low Permeability Soil Layer resulting from density testing shall be backfilled with calcium bentonite powder or granules or the soil-calcium bentonite mix furnished by the Contractor and compacted by hand tamping.

3.06 PROTECTION OF WORK

- A. Avoid crusting and desiccation cracking of compacted Low Permeability Soil Layer. Regularly moisture condition the surface of the compacted Low Permeability Soil. If cracks wider than the thickness of a 10 cent piece are observed, moisture condition and recompact the surface. Seal roll the surface of the Low Permeability Soil Layer to reduce evaporation, or alternatively protect exposed surfaces using light-colored or translucent membranes, that will inhibit drying.
- B. Repair areas of crusting or desiccation cracks deeper than 2". Scarify the surface of such areas to a depth of 2" or to the depth of the desiccation cracks, whichever is greater, and then moisture condition, process, and recompact the area in accordance with the requirements of this Section.
- C. Using the specified equipment, the Contractor shall coordinate sealing of the compacted Low Permeability Soil Layer surface at the end of every working day and when precipitation is forecast.
- D. Compacted Low Permeability Soil Layer may be protected using tarping, Polyvinyl Chloride (PVC) geomembrane, or other means selected by the Contractor, to shed rainfall runoff during periods of extended rain.
- E. If the compacted Low Permeability Soil Layer surface cannot be maintained in a moist condition to prevent desiccation, a soil protection layer shall be placed over the compacted Low Permeability Soil Layer if construction of overlying layers or lifts is to be delayed by more than 10 calendar days. Compact the soil protection layer by tracking with a bulldozer. The loose thickness of the soil protection layer shall be $4" \pm 1"$. The soil protection layer can also be used to protect Low Permeability Soil Layer against excessive rainfall.
- F. Remove the compacted soil protection layer prior to placement of overlying lifts. The soil protection layer may be removed in panels or areas in coordination with ongoing construction. Where the soil protection layer is removed, prepare the surface to receive an overlying lift as required by this Section.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	12 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

G. Synthetic sealants or other chemical treatments to the compacted Low Permeability Soil Layer material shall not be applied.

3.07 SURVEY CONTROL

- The Contractor shall provide as-built documentation for the top surface and A. bottom surface of the Low Permeability Soil Layer. In addition, Contractor shall also provide thickness measurements or calculations for the Low Permeability Soil Layer as it is being constructed. These thickness values measured or calculated during construction are less likely to be affected by the settlement of the soft foundation material than the elevation measurements of the top of the Low Permeability Soil Layer taken after the construction. Therefore, the thickness measurements or calculations performed during construction shall be used to verify that the minimum thickness requirements are met. The elevation measurements of the top of the Low Permeability Soil Layer taken after the construction shall be used to verify general conformance with base slopes to meet positive drainage requirements. The elevation measurements shall be performed at a maximum spacing of 50 ft by 50 ft. The thickness measurements or calculations shall be performed at a maximum spacing of 100 ft by 100 ft. In areas where the design clay thickness is 18 inches or less, an approximately 18-inch square steel plate will be placed between the top of the subgrade and the bottom of the clay on a 100-ft x 100-ft grid. The top of subgrade will be surveyed before placing clay using GPS on a 50-ft x 50-ft grid. After clay placement, the top of the clay layer will be surveyed on the same 50-ft x 50-ft grid. In addition, at the steel plate locations (i.e., on the 100-ft x 100-ft grid), a clay thickness measurement will be taken by hand augering down to the steel plate. Hand auger holes will be filled with a bentonite mixture, as specified by the Engineer. In areas where the clay thickness is greater than 18 inches, alternate methods will be used to estimate clay thickness, as specified in Appendix N, Geotechnical Instrumentation and Monitoring Plan.
- B. Provide survey information for Engineer to confirm the thicknesses and grades of complete areas. A maximum of 3 working days shall be allowed for the Engineer to confirm and accept the survey results.

3.08 TOLERANCES

- A. Construct the Low Permeability Soil Layer to within minus 0 to plus 2" of the thicknesses shown on the Project Drawings.
- B. Construct the finished surface of Low Permeability Soil Layer slopes to a tolerance of +0.2% of the slopes indicated on the Project Drawings when measured at any point along a 50 feet straight-edge. These tolerances shall not

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	13 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11

result in slopes that are less than the minimum slopes required on the Project Drawings.

C. Provide survey information for Engineer to confirm the thicknesses and slopes of complete areas 3 working days prior to the start of the covering layers.

[END OF SECTION]

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	14 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11



Figure No. 1. Minimum Required Peak Interface/Internal Friction Angles

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02250	Page:	15 of 15
Specification Title	Low Permeability Soil Layer	Date:	21 April 11



Figure No. 2. Minimum Required Residual Interface/Internal Friction Angles

SPECIFICATION NO: SECTION 02300

SPECIFICATION TITLE: GRAVEL DRAINAGE LAYER

PROJECT NO: 444853

PROJECT TITLE: ONONDAGA LAKE SCA FINAL DESIGN

CLIENT: HONEYWELL, INC.

					APPROVAL	S
Issue	Date	Pages	Issue Description	Prepared	Checked	Approved
0	12Jul10	8	Original	JMS	RK	
1	13Oct10	8	 Issued for Construction Added cover page and updated headers. Section 3.03A has been revised. 	JMS	RK	JFB
2	21Apr11	8	 Response to Comments Page 5, Item 2.01B: Replaced "100% passing the 3" sieve" with "100% passing the 4" sieve". Section 1.05A updated. 	JMS	RK	JFB
Entire Specification Issued this Revision		ion ion	SPECIFICATION ISSUED FOR:			
Revised Pages Only Issued this Revision		nly ion	In-house ReviewClient Review/ApInformation Only	proval [☐ Bid ☐ Constructio ☐ <i>Other</i>	on

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02300	Page:	2 of 8
Specification Title	Gravel Drainage Layer	Date:	21 April 11

SECTION 02300

GRAVEL DRAINAGE LAYER

PART 1 – GENERAL

1.01 SCOPE OF WORK

A. The work covered in this Section consists of furnishing and placing the layer of granular material within the liner system, which is part of the Sediment Consolidation Area (SCA). The granular material is placed on top of the geotextile cushion in accordance with the Project Specifications and Drawings and in conformity with the lines, grades, thicknesses, and typical cross-sections shown on the plans or established by the Engineer.

1.02 RELATED WORK

- A. Work in this section includes, but is not limited to:
 - 1. Section 01030 Environmental Protection
 - 2. Section 01300 Submittal Procedures
 - 3. Section 01620 Health and Safety Requirements
 - 4. Section 02100 Site Clearing
 - 5. Section 02200 Earthwork
 - 6. Section 02250 Low Permeability Soil Layer

1.03 REFERENCES

- A. Latest version of American Society for Testing and Materials (ASTM) Standards:
 - 1. ASTM C 136 Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
 - 2. ASTM D 75 Standard Practice for Sampling Aggregates
 - 3. ASTM D 2434 Standard Test Method for Permeability of Granular Soils (Constant Head).
 - 4. ASTM D 2487 Standard Classification of Soils for Engineering Purposes (Unified Soil Classification System).
 - 5. ASTM D 3042 Standard Test Method for Insoluble Residue in Carbonate Aggregate.

1.04 SUBMITTALS

A. The Contractor shall submit the following information to Engineer for review and approval in accordance with Section 01300 – Submittal Procedures and as
 Onondaga Lake SCA Final Design
 Gravel Drainage Layer
 O2300-2
 Geosyntec
Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02300	Page:	3 of 8
Specification Title	Gravel Drainage Layer	Date:	21 April 11

elsewhere specified in this Section 30 calendar days prior to initiating Gravel Drainage Layer activities.

- 1. Handling and stockpiling methods to minimize particle segregation;
- 2. Equipment and methods for management of various stockpiles. Management of stockpiles shall also include methods to measure and monitor material stockpiles;
- 3. Equipment and methods to load and haul material from the material stockpiles;
- 4. Equipment and methods to place the material;
- 5. Repair procedures;
- 6. Proposed offsite borrow source(s);
- 7. Coordination of survey requirements for the work;
- 8. Locations of on-site temporary soil stockpile areas;
- 9. Coordination of construction activities with surface-water management and erosion and sediment control measures;
- 10. Schedule for construction activities; and
- 11. Quality Control Work Plan.
- B. The Contractor shall be responsible for the adequacy and safety of the methods.
- C. Test results as specified herein shall be submitted to the Engineer for review within two (2) working days of receipt of results. The Contractor shall not deliver material to the site prior to submission and approval by the Engineer of the geotechnical and analytical chemistry test results.

1.05 CONSTRUCTION QUALITY CONTROL

- A. The Contractor shall submit a Quality Control (QC) Workplan for review to the Engineer. Once instituted, the Contractor shall use the QC Workplan to ensure that the Work performed under the contract meets the requirements of the Contract Documents.
- B. The Contractor shall submit the name of a qualified Independent Testing Laboratory (ITL) to the Engineer for review.
 - 1. The Contractor shall submit to the Engineer for approval, the company name, address, and qualifications of the selected ITL proposed for use at the project. Included in this submittal will be the names and qualifications of the individuals who are proposed for assignment to the site. The Engineer reserves the right to request other information regarding the qualifications of the ITL for use in the evaluation process.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02300	Page:	4 of 8
Specification Title	Gravel Drainage Layer	Date:	21 April 11

C. Sampling

- 1. The Contractor shall be responsible for collecting samples and conducting tests using a qualified ITL to document material property compliance with the specifications.
- 2. Representative samples of each specific material type from each specific material source will be obtained by compositing at least five randomly selected individual samples of approximately equal weight. The total composite sample mass shall be at least the minimum size required to conduct all of the required material property tests for that material type. Each of the individual samples will be obtained from within the boundaries of the material mass that the composite sample represents.
- 3. Contractor quality control samples may be obtained from in situ samples for pre-approval of a dedicated borrow source area. The sampling methodology and means for assuring the material dedication to the project shall be submitted to the Engineer for approval prior to the commencement of sampling.
- 4. Contractor quality control samples may also be obtained from dedicated stockpiles or storage/transportation vessels. The sampling methodology and means for assuring the material dedication to the project shall be submitted to the Engineer for approval prior to the commencement of sampling.
- D. Minimum Sample Frequency
 - 1. QC testing per Part 360 will require a representative sample obtained and tested at the following frequencies (with a minimum of 1 sample from each borrow source area with consistent appearance):

One soil particle size analysis and soil classification for every 1,000 cubic yards of gravel drainage material placed; and one laboratory constant head permeability test for every 2,500 cubic yards of gravel drainage material placed.

- E. Material Property Testing
 - 1. Each composite sample shall be tested for material properties as defined in the section 2.01.E.
- F. General
 - 1. No imported materials shall be delivered to the project site before the required material property testing for that batch has been provided to the Engineer and written approval received from the Engineer. Unapproved material shall be removed from the site at the Contractor's expense.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02300	Page:	5 of 8
Specification Title	Gravel Drainage Layer	Date:	21 April 11

2. Contractor shall be responsible for repairing or reconstructing the deficiencies at his own expense to meet this specification and other Contract Documents.

1.06 CONSTRUCTION QUALITY ASSURANCE

- A. The Engineer shall conduct quality assurance sampling on Gravel Drainage Layer materials.
 - 1. The Contactor shall provide access and support for the sampling and testing.
 - 2. The Engineer shall have the right to visit the borrow source at any time during borrow pit working hours to observe mining, manufacturing, stockpiling or loading operations.

PART 2 – PRODUCTS

2.01 MATERIALS

- A. The drainage layer material shall be reasonably free of thin, flat, or elongated pieces, shall contain no organic matter, or soft friable particles, and shall not contain visible asbestos or hydrocarbons.
- B. Drainage layer material shall be classified as GW or GP in accordance with the Unified Soil Classification System (USCS) per ASTM D 2487 and shall have 100% passing the 4" sieve, less than 5% passing the #4 sieve, and less than 3% passing the #200 sieve. Alternate gravel gradations may be allowed based on approval of the Design Engineer.
- C. Drainage layer material shall have a minimum hydraulic conductivity of 10 centimeters per second (cm/s) based on laboratory permeability testing conducted in accordance with ASTM D 2434.
- D. The required gradation shall be obtained by screening or blending processes as may be necessary. Crushing may be allowed based on approval by the Engineer.
- E. The Contractor shall perform the following tests, prior to material being delivered to the site, at the frequency specified in Section 1.05:
 - 1. Grain size (ASTM C 136)
 - 2. Hydraulic Conductivity (ASTM D 2434)
- F. The Contractor shall perform a minimum of one round of the following tests per borrow source, prior to material being delivered to the site:

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02300	Page:	6 of 8
Specification Title	Gravel Drainage Layer	Date:	21 April 11

- 1. Certification and test results certifying that the material meets Table 375-6.8(b) "Restricted Use Soil Cleanup Objectives" in NYSDEC Subpart 375. All test results shall be below the Commercial cleanup objective concentrations provided in this table.
- G. These control tests will be performed at each visual or textural change in source material, or as directed by the Engineer. Test results shall be submitted to the Engineer in accordance with Part 1.04.

2.02 EQUIPMENT

- A. Furnish equipment to haul, place, spread, and compact drainage layer materials.
- B. Low ground pressure equipment shall be used to place, spread and compact drainage layer materials, as approved by the Engineer. Areas such as access roads that may have truck traffic shall have at least 24 inches of gravel thickness before such traffic can be allowed.

PART 3 – EXECUTION

3.01 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Drainage layer material delivered to the site may be stockpiled in areas designated on the Project Drawings or other areas approved by the Engineer.
- B. Stockpiled drainage material shall be managed and controlled to prevent mixing with other materials in accordance with the Contractor's procedures.

3.02 MATERIAL PLACEMENT

- A. The drainage layer materials shall not be placed until Engineer has reviewed and approved the initial source certifications, required test data for material stockpiled at the site, and required test data and submittals, including survey information, for the underlying soil layer.
- B. Place the drainage layer material directly on top of the underlying geotextile layer, as shown on the Project Drawings and then carefully spread using equipment and procedures that will not cause damage or rutting to the underlying geotextile. The Gravel Drainage Layer thicknesses at each location shall be in accordance with the Project Drawings and shall not be less than 12 inches at any location. Areas such as access roads that may have truck traffic shall have at least 24 inches of gravel thickness before such traffic can be allowed.
- C. The drainage layer material shall be delivered as a uniform mixture and shall be placed to limit segregation of materials and the formation of pockets of coarse

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02300	Page:	7 of 8
Specification Title	Gravel Drainage Layer	Date:	21 April 11

and fine materials. Placement of the materials in windrows or layers shall be done to limit the distance that the drainage layer materials must be spread to achieve the required thickness.

- D. Drainage layer materials shall not be hauled directly on the underlying layers.
- E. Spread the drainage layer material over the underlying geotextile by pushing the material forward to cascade rather than be shoved across the underlying layer.
- F. Drainage layer material shall be placed in loose lift thicknesses of one foot or greater to the lines, thicknesses and grades shown on the drawings and as approved by Engineer. The thickness of the Drainage Layer at any location shall be measured perpendicular to the plane of the slope at each location. Due to the compressible nature of the foundation, a strict conformance with the design elevations is not required. Gravel Drainage Layer material can be used to locally adjust the slopes to improve stability during filling of geo-tubes as needed.
- G. Drainage layer material should be placed in coordination with the Engineer. Gravel shall not be placed when snow cover is present on the geotextile cushion. Gravel placement shall continue after the snow cover has melted sufficiently to proceed with placement. All safety procedures regarding operating equipment under snow events shall be followed.

3.03 SURVEY CONTROL

- A. Contractor shall provide as-built documentation for the top surface of the Gravel Drainage Layer. In addition, Contractor shall also provide thickness measurements or calculations for the Gravel Drainage Layer as it is being constructed. Thickness measurements shall be obtained by calculating the difference between the elevation of the top of the Low Permeability Soil Layer and the top of the Gravel Drainage Layer. These elevations shall be measured using GPS instrumentation on the equipment grading the Gravel Drainage Layer. The thickness measurements or calculations performed during construction shall be used to verify that the minimum thickness requirements are met. The elevation measurements of the top of the Gravel Drainage Layer taken after construction shall be used to verify general conformance with base slopes.
- B. Provide survey information for Engineer to confirm the thicknesses and grades of complete areas. A maximum of 3 working days shall be allowed for the Engineer to confirm and accept the survey results.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02300	Page:	8 of 8
Specification Title	Gravel Drainage Layer	Date:	21 April 11

3.04 TOLERANCES

- A. Construct the finished surface of the Gravel Drainage Layer slopes to a tolerance of $\pm -0.2\%$ of the slopes indicated on the Project Drawings when measured at any point along a 50 feet straight-edge.
- B. Tolerance requirement may be waived by the Engineer to achieve grades in a manner to facilitate placement of geotextile tubes.

[END OF SECTION]

SPECIFICATION NO: SECTION 02710

SPECIFICATION TITLE: GEOTEXTILE CUSHION

PROJECT NO: 444853

PROJECT TITLE: ONONDAGA LAKE SCA FINAL DESIGN

CLIENT: HONEYWELL, INC.

					APPROVAL	S
Issue	Date	Pages	Issue Description	Prepared	Checked	Approved
0	12Jul10	8	Original	JMS	RK	
1	13Oct10	8	 Issued for Construction Added cover page and updated headers. 	JMS	RK	JFB
2	21Apr11	8	 Response to Comments Page 4, Item D. "LLDPE" changed to "HDPE". Page 8, Table 1. Minimum mass per unit area changed to 24 oz/yd². 	JMS	RK	JFB
 Entire Specification Issued this Revision 		tion sion	SPECIFICATION ISSUED FOR:			
Revised Pages Only Issued this Revision)nly sion	In-house Review Client Review/Ap Information Only	oproval D	Bid Construct <i>Other</i>	tion

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02710	Page:	2 of 8
Specification Title	Geotextile Cushion	Date:	21 April 11

SECTION 02710

GEOTEXTILE CUSHION

PART 1 – GENERAL

1.01 SCOPE OF WORK

A. This Section describes the materials, installation, and testing requirements to perform the installation, quality control, and maintenance of the geotextile cushion for the base liner system of the Sediment Consolidation Area (SCA).

1.02 RELATED WORK

- A. Work in this section includes, but is not limited to:
 - 1. Section 01030 Environmental Protection
 - 2. Section 01300 Submittal Procedures
 - 3. Section 01620 Health and Safety Requirements
 - 4. Section 02100 Site Preparation
 - 5. Section 02740 Geomembrane Liner
 - 6. Section 02225 Gravel Drainage Layer

1.03 REFERENCES

- A. Latest version of American Society for Testing and Materials (ASTM) Standards:
 - 1. ASTM D 4355 "Standard Test Method for Deterioration of Geotextiles by Exposure to Light, Moisture, and Heat in a Xenon Arc Type Apparatus".
 - 2. ASTM D 4533 "Standard Test Method for Trapezoid Tearing Strength of Geotextiles".
 - 3. ASTM D 4632 "Standard Test Method for Grab Breaking Load and Elongation of Geotextiles".
 - 4. ASTM D 4833 "Standard Test Method for Index Puncture Resistance of Geomembranes and Related Products".
 - 5. ASTM D 4873 "Standard Guide for Identification, Storage, and Handling of Geosynthetic Rolls and Samples".
 - 6. ASTM D 5261 "Standard Test Method for Measuring Mass per Unit Area of Geotextiles".

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02710	Page:	3 of 8
Specification Title	Geotextile Cushion	Date:	21 April 11

7.	ASTM D 5321	Standard Test Method for Determining the Coefficient
		of Soil and Geosynthetic or Geosynthetic and
		Geosynthetic Friction by the Direct Shear Method.
8.	ASTM D 5514	Standard Test Method for Large Scale Hydrostatic
		Puncture Testing of Geosynthetics.
9.	ASTM D 6193	"Standard Practice for Stitches and Seams".

1.04 SUBMITTALS

- A. Submit the following to the Engineer for review not less than 21 calendar days prior to shipment.
 - 1. Geotextile Manufacturer and product name.
 - 2. Certification of minimum average roll values and the corresponding test procedures for all geotextile properties listed in Table 1.
 - 3. Projected geotextile delivery dates.
 - 4. Manufacturer quality control tests and manufacturer certifications per Section 2.02.
- B. Submit to the Engineer for review at least 14 calendar days prior to geotextile shipment, manufacturing quality control certificates for each roll of geotextile as specified in this Section. This documentation must be reviewed and approved by the Engineer to satisfy the requirements of these specifications prior to transporting any geotextile to the site.

1.05 AS-BUILT DOCUMENTATION

- A. The Contractor shall provide as-built revisions to the Project Drawings in accordance with Section –01300 Submittal Procedures.
- B. In addition to preparation of as-built revisions to the Project Drawings, the Contractor shall provide as-built documentation for the placed geotextiles.

1.06 CONSTRUCTION QUALITY ASSURANCE

- A. The installation of geotextiles will be monitored by the Engineer as required in the CQA Plan.
- B. The Engineer will perform material conformance testing of the geotextiles.
- C. The Contractor shall be aware of the activities required of the Engineer by the CQA Plan and shall account for these activities in the construction schedule.
- D. The Contractor shall correct all deficiencies and nonconformances identified by the Engineer at no additional cost to the Owner.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02710	Page:	4 of 8
Specification Title	Geotextile Cushion	Date:	21 April 11

PART 2 – PRODUCTS

2.01 GEOTEXTILE

- A. Furnish geotextile products with minimum average roll values (95 percent lower confidence limit) meeting or exceeding the required property values in Table 1.
- B. Furnish geotextiles that are manufactured from first quality polymers, with not more than 20 percent reclaimed polymer used in production.
- C. Furnish polymeric threads for stitching that are ultra-violet (UV) light stabilized to at least the same requirements as the geotextile to be sewn. Furnish polyester or polypropylene threads that have a minimum size of 2,000 denier.
- D. Furnish geotextile material that meets the minimum required peak and residual internal/interface friction angles shown in Section 02250: Low Permeability Soil Layer when tested as a layered sandwich representing the base liner system of the SCA (low permeability soil, 60-mil HDPE geomembrane, geotextile cushion and gravel drainage layer) in accordance with ASTM D 5321. This test shall be performed at the frequency specified in Section 02250.

2.02 MANUFACTURING QUALITY CONTROL

- A. Sample and test the geotextile to demonstrate that the material conforms to the requirements of this Section.
- B. Perform manufacturing quality control tests to demonstrate that the geotextile properties conform to the values specified in Table 1. Perform as a minimum, the following manufacturing quality control tests at a minimum frequency as shown:

Test	Procedure	Frequency (min)
Mass per unit area	ASTM D 5261	one per 90,000 ft^2
Grab strength	ASTM D 4632	one per 90,000 ft ²
Tear strength	ASTM D 4533	one per 90,000 ft ²
Puncture strength	ASTM D 4833	one per 90,000 ft ²
UV resistance	ASTM D 4355	one per formulation

C. Submit quality control certificates signed by the geotextile Manufacturer quality control manager. Certificates shall state that the material is resistant to UV exposure and that the geotextiles are continuously inspected and are needle-free.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02710	Page:	5 of 8
Specification Title	Geotextile Cushion	Date:	21 April 11

The quality control certificates shall also include: lot, batch, and roll number and identification; and results of manufacturing quality control tests including description of test methods used.

- D. Do not supply any geotextile roll that does not comply with the manufacturing quality control requirements.
- E. If a geotextile sample fails to meet the quality control requirements of this Section, sample and test rolls manufactured at the same time or in the same lot as the failing roll. Continue to sample and test the rolls until the extent of the failing rolls are bracketed by passing rolls. Do not supply failing rolls.

2.03 PACKAGING AND LABELING

- A. Supply geotextiles in rolls wrapped in relatively impermeable and opaque protective wrapping. Wrapping which becomes torn or damaged shall be repaired with similar materials.
- B Mark or tag geotextile rolls in accordance with ASTM D 4873 with the following information:
 - 1. manufacturer's name;
 - 2. product identification;
 - 3. lot or batch number;
 - 4. roll number; and
 - 5. roll dimensions.
- C. Geotextile rolls not labeled in accordance with this Section or on which labels are illegible shall be rejected and replaced.

2.04 HANDLING AND STORAGE

- A. Protect geotextiles from sunlight, moisture, excessive heat or cold, puncture, mud, dirt, and dust or other damaging or deleterious conditions. Follow all geotextile manufacturer recommendations for handling and storage.
- B. Store geotextile rolls on pallets or other elevated structures. Do not store geotextile rolls directly on the ground.
- C. Outdoor storage of rolls shall not exceed the manufacturer's recommendation or longer than 6 months, whichever is less.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02710	Page:	6 of 8
Specification Title	Geotextile Cushion	Date:	21 April 11

PART 3 – EXECUTION

3.01 PLACEMENT

- A. Handle geotextiles so as to ensure they are not damaged in any way.
- B. Take necessary precautions to prevent damage to underlying layers including rutting during placement of the geotextiles.
- C. After unwrapping the geotextiles from their opaque cover, do not leave them exposed for a period in excess of 14 calendar days.
- D. If white colored geotextiles are used, take precautions against "snow blindness" of personnel. Precautions against "snow blindness" include wearing sunglasses and avoiding exposure for long periods of time.
- E. Anchor or weight geotextile with sandbags, or the equivalent, to prevent damage from wind. Install sandbags during placement and maintain them until overlying material is placed. Geotextiles installed on slopes shall be secured in anchor trenches, as shown on the drawings.
- F. Examine the geotextile surface after installation to ensure that no potentially harmful foreign objects are present. Remove any such objects and replace any damaged geotextiles.

3.02 SEAMS AND OVERLAPS

- A. Seams shall be overlapped or seamed. When seamed, continuously overlap a minimum of 6 inches and sew geotextiles (i.e., spot sewing is not allowed) using a "single prayer" seam. Sew seams using Stitch Type 401 as per ASTM D 6193. When overlapped, the geotextile panels need to be shingled in the direction of fill placement to prevent the top geotextile from peeling as the fill is spread. Overlaps (without seams) shall be at least 3 feet long.
- B. Do not install horizontal seams on slopes that are steeper than 10 horizontal to 1 vertical. Seams shall be along, not across, the slopes.
- C. All geotextiles should be placed with all seams up to facilitate inspection and repair.

3.03 REPAIR

A. Repair any holes or tears in the geotextiles using a patch made from the same geotextile material. Extend geotextile patches a minimum of 1 foot beyond the damaged area. Sew geotextile patches into place no closer than 1 inch from any

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02710	Page:	7 of 8
Specification Title	Geotextile Cushion	Date:	21 April 11

panel edge. Should any tear exceed 50 percent of the width of the roll, remove, and replace that roll.

B. Remove any soil or other material that may have penetrated the torn geotextiles.

3.04 PLACEMENT OF SOIL AND AGGREGATE MATERIALS

- A. Place soil materials on top of geotextiles in such a manner as to ensure that:
 - 1. the geotextiles and the underlying materials are not damaged; and
 - 2. slippage does not occur between the geotextile and the underlying layers during placement.
- B. Spread soil on top of the geotextile to cause the soil to cascade over the geotextile rather than be shoved across the geotextile.
- C. Equipment placing soil and aggregate material on geotextile shall be as approved by the Engineer.
- D. Place aggregate over geotextile cushion as indicated on the Project Drawings prior to trafficking.

[END OF SECTION]

TABLE 1. REQUIRED PROPERTY VALUES FOR GEOTEXTILE CUSHION

PROPERTIES	QUALIFIER	UNITS	SPECIFIED ⁽¹⁾ VALUES	TEST METHOD		
Туре	•		•			
nonwoven needlepunched				(-)		
Polymer composition	Minimum	%	95 polypropylene or polyester by weight	(-)		
Mass per unit area	Minimum	oz/yd ²	24	ASTM D 5261		
Mechanical Requirements						
Grab strength	minimum	lb	230	ASTM D 4632 ⁽³⁾		
Tear strength	minimum	lb	95	ASTM D 4533 ⁽⁴⁾		
Puncture strength	minimum	lb	a load equivalent to 5,000 psf.	ASTM D 4833 ⁽⁵⁾		
Shear strength	minimum		See Note 2.	ASTM D 5321		
Durability	•	•				
Ultraviolet Resistance	minimum	%	70	ASTM D 4355		

Notes:

(6)

- (1) All values represent minimum average roll values.
- (2) The required peak and residual shear strength parameters are included in a figure as part of Section 02215.
- (3) Minimum of values measured in machine and cross machine directions with 1 inch clamp on Constant Rate of Extension (CRE) machine.
- (4) Minimum value measured in machine and cross machine direction.
- (5) Tension testing machine with a 1.75-inch diameter ring clamp, the steel ball being replaced with 0.31-inch diameter solid steel cylinder with flat tip centered within the ring clamp.

mm	=	millimeter
%	=	percent
oz/yd ²	=	ounce per square yard
sec	=	second
lb	=	pound
psi	=	pound per square inch

SPECIFICATION NO: SECTION 02772

SPECIFICATION TITLE: GEOSYNTHETIC CLAY LINER

PROJECT NO: 444853

PROJECT TITLE: ONONDAGA LAKE SCA FINAL DESIGN

CLIENT: HONEYWELL, INC.

				l	APPROVAL	~S
Issue	Date	Pages	Issue Description	Prepared	Checked	Approved
0	12Jul10	9	Original	JMS	RK	
1	13Oct10	9	 Issued for Construction Added cover page and updated headers. 	JMS	RK	JFB
2	21Apr11	9	Issued with SCA Final Design Submittal	JMS	RK	JFB
Image: Specification Issued this RevisionSPECIFICATION ISSUED FOR:						
Revised Pages Only Issued this Revision			In-house Review Client Review/Ap Information Only	proval 🛛	BidConstructionOther	on

Г

Onondaga Lake SCA Final Design April 21, 2011 Geosyntec 1

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02772	Page:	2 of 9
Specification Title	Geosynthetic Clay Liner	Date:	21 April 11

SECTION 02772

GEOSYNTHETIC CLAY LINER

PART I - GENERAL

1.01 SCOPE

- A. This Section describes the materials, installation, and testing requirements to perform the installation and quality control of the geosynthetic clay liner (GCL) component of the liner system. The GCL shall be placed in accordance with the Project Specifications and Drawings. The Contractor shall furnish all labor, materials, equipment, supervision, and incidentals necessary to perform the scope of work.
- B. All GCL material placed as a part of this project shall be placed, tested, and documented in accordance with this Section unless specifically approved by the Engineer.

1.02 RELATED WORK

- A. Work in this section includes, but is not limited to:
 - 1. Section 01300 Submittal Procedures
 - 2. Section 01620 Health and Safety Requirements
 - 3. Section 02250 Low Permeability Soil Layer
 - 4. Section 02740 Geomembrane Liner

1.03 REFERENCES

A. Latest version of American Society for Testing and Materials (ASTM) Standards:

1.	ASTM D 4643.	"Standard Test Method for Determination of Water
		(Moisture) Content of Soil by Microwave Oven
		Method."
2.	ASTM D 5261.	"Standard Test Method for Measuring Mass Per Unit
		Area of Geotextiles."
3.	ASTM D 5887.	"Standard Test Method for Measurement of Index
		Flux through Saturated Geosynthetic Clay Liner
		Specimens Using a Flexible Wall Permeameter."
4	ASTM D 5890.	"Standard Test Method for Swell Index of Clay
		Mineral Component of Geosynthetic Clay Liners."
5.	ASTM D 5891.	"Standard Test Method for Fluid Loss of Clay
		Component of Geosynthetic Clay Liners."

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02772	Page:	3 of 9
Specification Title	Geosynthetic Clay Liner	Date:	21 April 11

6.	ASTM D 5993.	"Standard Test Method for Measuring Mass per Unit
		of Geosynthetic Clay Liner."
7.	ASTM D 6496.	"Standard Test Method for Determining Average
		Bonding Peel Strength Between the Top and Bottom
		Layers of Needle-Punched Geosynthetic Clay
		Liners."
8.	ASTM D 6768.	"Standard Test Method for Tensile Strength of
		Geosynthetic Clay Liners."

1.04 SUBMITTALS

- A. Submit the following information to the Engineer for review not less than 45 calendar days prior to use for all additional GCL furnished.
 - 1. Manufacturing certificates for each shift's production of GCL, signed by the Manufacturer quality control manager, and notarized.
 - 2. Certificate shall include:
 - a. roll numbers and identification;
 - b. sampling procedures; and
 - c. results of Manufacturer quality control tests, including descriptions of the test methods used (the Manufacturer quality control tests to be performed are given in Part 2 of this Section).
- B. Submit to the Engineer for review the following information from the Installer for the geosynthetic clay liner within 14 calendar days prior to mobilization of the Installer to the site:
 - 1. installation schedule;
 - 2. installation work plan, including:
 - a. list of placement equipment proposed for this project;
 - b. description of installation methods;
 - c. coordination of geosynthetic clay liner installation with installation of low permeability soil layer and geomembranes and gravel drainage layers;
 - d. storage methods in accordance with Manufacturer's recommendations;
 - e. average daily placement anticipated for this project; and
 - f. quality assurance methods and procedures.
 - 3. A list of 10 completed facilities for which the Installer has installed a geosynthetic clay liner. The following information shall be provided for each facility:
 - a. the name and purpose of the facility, its location, and dates of installation;
 - b. the names of the owner, project manager, and geosynthetic clay liner Manufacturer;

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02772	Page:	4 of 9
Specification Title	Geosynthetic Clay Liner	Date:	21 April 11

- c. name of the supervisor of the installation crew;
- d. thickness and surface area of installed geosynthetic clay liner; and
- e. duration of installation.
- 4. Resumes of the Installer Superintendent and quality assurance inspector proposed for this project, including dates and duration of employment.
- C. Submit to the Engineer for review low permeability soil layer acceptance certificates, signed by the Installer, for each area to be covered by the geosynthetic clay liner prior to that area being covered.

1.05 AS-BUILT DOCUMENTATION

- A. The Contractor shall submit as-built revisions to the Project Drawings in accordance with Section –01300 Submittal Procedures.
- B. In addition to preparation of as-built revisions to the Project Drawings, the Contractor shall provide as-built documentation for the placed GCL.

1.06 CONSTRUCTION QUALITY ASSURANCE

- A. The construction of the GCL will be monitored as required in the CQA Plan.
- B. The Engineer will perform material conformance testing of GCL materials and installation quality assurance testing of the GCL seams, as required in the CQA Plan.
- C. The Contractor shall be aware of the activities required of the Engineer by the CQA Plan and shall account for these activities in the construction schedule.
- D. The Contractor shall correct all deficiencies and nonconformances identified by the Engineer at no additional cost.

PART 2 - PRODUCTS

2.01 GEOSYNTHETIC CLAY LINER

- A. The Contractor shall furnish geosynthetic clay liner materials that meet the following requirements:
 - 1. Geosynthetic clay liner will consist of internally-reinforced bentonite core with nonwoven geotextile and woven geotextile backings.
 - 2. Geosynthetic clay liner will have properties that comply with the required values shown in Table 02772-1.
 - 3. Provide granular or powdered bentonite in accordance with the manufacturer's specifications for geosynthetic clay liner.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02772	Page:	5 of 9
Specification Title	Geosynthetic Clay Liner	Date:	21 April 11

2.02 MANUFACTURING QUALITY CONTROL

A. Sample and test the GCL, to demonstrate that its properties conform to the values specified in Table 02772-1. Perform the following quality control tests at a minimum frequency shown:

Component	Test	Procedure	Frequency (min)
Bentonite	Bentonite Moisture Content	ASTM D 4643	one per 5,000 yd^2
Bentonite	Bentonite Fluid Loss	ASTM D 5891	one per 110,000 lb
Bentonite	Bentonite Free Swell	ASTM D 5890	one per 110,000 lb
GCL	Bentonite Mass/Area	ASTM D 5993	one per 5,000 yd^2
GCL	Tensile Strength	ASTM D 6768	one per 25,000 yd^2
GCL	Average Peel Strength	ASTM D 6496	one per 5,000 yd^2
GCL	Index Flux	ASTM D 5887	one per 30,000 yd^2
Geotextile	Cap Mass/Area	ASTM D 5261	one per $25,000 \text{ yd}^2$
Geotextile	Carrier Mass/Area	ASTM D 5261	one per $25,000 \text{ yd}^2$

- B. If a GCL sample fails to meet the quality control requirements of this Section, sample and test rolls manufactured at the same time as the failing roll. Continue to sample and test the rolls until the extent of the failing rolls are bracketed by passing rolls. Do not supply any failing rolls.
- C. Permit the Engineer to visit the manufacturing plant for project specific visits. If possible, such visits will be prior to, or during, the manufacturing of the geomembrane rolls for this project.

2.03 PACKAGING

- A. Geosynthetic clay liner rolls will be wrapped in impermeable and opaque protective covers.
- B. Each geosynthetic clay liner roll will be marked or tagged with the following information:
 - 1. manufacturer's name;
 - 2. product identification;
 - 3. lot number;
 - 4. roll number;
 - 5. roll weight; and
 - 6. roll dimensions.
- C. Geosynthetic clay liner rolls not labeled in accordance with this Section or on which labels are illegible will be rejected and replaced. Contractor shall notify the Engineer of any missing or illegible labels.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02772	Page:	6 of 9
Specification Title	Geosynthetic Clay Liner	Date:	21 April 11

2.04 ACCEPTANCE, HANDLING, AND STORAGE

- A. Contractor shall inspect and inventory the geosynthetic clay liner materials and the manner in which they are stored. Contractor shall provide a written letter of acceptance within 30 days to the Engineer if material is acceptable for installation. Contractor shall also notify the Engineer in writing within 30 days of any geosynthetic clay liner material not acceptable for installation.
- B. Protection and preservation of geosynthetic clay liner materials shall include, but not be limited to:
 - 1. handling, storage, and care for the geosynthetic clay liner in a manner that does not cause hydration or damage;
 - 2. protection of the geosynthetic clay liner from UV, moisture, excessive heat or cold, dirt, puncture, or other damaging or deleterious conditions; and
 - 3. storage of the geosynthetic clay liner rolls on pallets or other elevated structures.
- C. Contractor shall unload, handle, and store geosynthetic clay liner material. Handling shall be performed such that damage to geosynthetic clay liner materials does not occur.

2.04 EQUIPMENT

A. Furnish equipment for acceptance, handling, storage, and installation of geosynthetic clay liner.

PART 3 - EXECUTION

3.01 SURFACE PREPARATION

- A. The Contractor shall provide certification in writing from the Geosynthetic Installer that the surface on which the geosynthetic clay liner will be installed is acceptable as described in this Section. This certification of acceptance shall be given to the Engineer prior to commencement of geosynthetic clay liner installation in the area under consideration.
- B. The surface in which the geosynthetic clay liner is to be placed shall be free of debris, roots, sticks, and loose stones and contain no ruts greater than ¹/₂-inch depth.
- C. Special care shall be taken to maintain the prepared foundation layer surface.
- D. Do not place the geosynthetic clay liner onto an area that has been softened by precipitation.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02772	Page:	7 of 9
Specification Title	Geosynthetic Clay Liner	Date:	21 April 11

3.02 PLACEMENT

- A. Do not place geosynthetic clay liner until the CQA Consultant completes conformance testing and confirmation of compliance, and performance testing and confirmation of compliance of underlying layers, including acceptance of Contractor's survey results for underlying layers.
- B. Cut the geosynthetic clay liner using a sharp utility blade. Do not damage underlying material during cutting and fully repair any such damage.
- C. Do not entrap stones or other foreign objects under the geosynthetic clay liner. Do not drag equipment across the exposed geosynthetic clay liner.
- D. Replace any geosynthetic clay liner that is damaged.
- E. Install geosynthetic clay liner with the woven geotextile backing in contact with the underlying layer. Install adjacent geosynthetic clay liner panels such that they are shingled down slope.
- F. Do not install the geosynthetic clay liner on a wet subgrade or in standing water. Prevent hydration of the bentonite core prior to completion of construction of at least one feet of gravel drainage layer.
- G. Do not install the geosynthetic clay liner during precipitation or other conditions that may cause hydration of the geosynthetic clay liner.
- H. Install the overlying geomembrane as soon as possible following geosynthetic clay liner installation. Cover all geosynthetic clay liner that is placed during a work day with overlying geomembrane. Cover and protect the edges of geosynthetic clay liner from hydration due to surface water runon.
- I. Remove and replace geosynthetic clay liner material that becomes hydrated. Hydration is defined by a moisture content of 40 percent or greater when measured in accordance with ASTM D 4643.

3.03 OVERLAPS

- A. On slopes steeper than 5 horizontal to 1 vertical, install geosynthetic clay liners continuously down the slope; that is, allow no horizontal seams on the slope.
- B. Allow no horizontal seams on the side slopes within 5 feet of the toe of a slope.
- C. Overlap geosynthetic clay liner in strict accordance with the Manufacturer's recommended methods. As a minimum, overlap adjacent panels at least 6 inches along the sides and 12 inches along the ends of installed panels.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02772	Page:	8 of 9
Specification Title	Geosynthetic Clay Liner	Date:	21 April 11

- D. Overlaps shall be shingled in the downward direction of the slope.
- E. Use of granular or powdered bentonite to enhance bonding at the seams shall be in accordance with the geosynthetic clay liner Manufacturer's recommendations.

3.04 MATERIALS IN CONTACT WITH THE GEOSYNTHETIC CLAY LINER

- A. Perform installation of other components in a manner that prevents damage to the geosynthetic clay liner.
- B. Do not drive equipment directly on the geosynthetic clay liner unless approved in writing by the Engineer. Damage due to equipment operating on the geosynthetic clay liner shall be repaired or replaced at no additional cost.
- C. Install the geosynthetic clay liner in appurtenant areas as shown on Project Drawings. Do not damage the geosynthetic clay liner while working around the appurtenances.

3.05 REPAIR

- A. Repair holes or tears in the geosynthetic clay liner by placing a geosynthetic clay liner patch under or over the hole. On slopes greater than 5 percent, the patch shall overlap the edges of the hole or tear by a minimum of 2 feet in all directions. On slopes 5 percent or flatter, the patch shall overlap the edges of the hole or tear by a minimum of 1 foot in all directions. Secure the patch as approved by the geosynthetic clay liner Manufacturer. Repairs shall be in strict accordance with Manufacturer's recommendations.
- B. Remove soil or other material that may have penetrated the torn geosynthetic clay liner.
- C. Do not nail or staple the patch.

3.06 CONSTRUCTION QUALITY REQUIREMENTS

A. The CQA Consultant will monitor geosynthetic clay liner installation in accordance with this Section and Construction Quality Assurance (CQA) Plan.

TABLE 02772-1

PROPERTIES	QUALIFIERS ⁽¹⁾	UNITS ⁽⁴⁾	SPECIFIED PROPERTY VALUES	TEST METHOD	
Bentonite Properties					
Bentonite Moisture Content	maximum	%	40	ASTM D 4643	
Bentonite Fluid Loss	maximum	mL	18	ASTM D 5891	
Bentonite Free Swell	minimum	ml/2g	24	ASTM D 5890	
Geosynthetic Clay Liner Properties					
Bentonite Mass/Area ⁽²⁾	MARV	lb/ft ²	0.75	ASTM D 5993	
Index Flux ⁽³⁾	maximum	$(m^3/m^2/s)$	1x10 ⁻⁶	ASTM D 5887	
Tensile Strength	MARV	lb/in	30	ASTM D 6768	
Average Peel Strength	minimum	lb/in	2.5	ASTM D 6496	
Geotextile Properties					
Cap Mass/Area	MARV	oz/yd ²	5.8	ASTM D 5261	
Carrier Mass/Area	MARV	oz/yd ²	3.0	ASTM D 5261	
Polymer Composition	minimum	%	95 polyester or polypropylene		

REQUIRED GEOSYNTHETIC CLAY LINER PROPERTY VALUES

Notes: 1. MARV = minimum average roll value.

2. Measured at a moisture content of 0 percent.

3. Index Flux testing is performed with de-aired tap water @ 5 psi maximum effective confining stress and 2 psi head.

4.	lb/ft ²	=	pounds	per	square	foot
----	--------------------	---	--------	-----	--------	------

cm/s	=	centimeter per second
g	=	grams
%	=	percent
lb	=	pound
lb/in.	=	pounds per inch
ml/2g	=	milliliters per two grams

[END OF SECTION]

Onondaga Lake SCA Final Design April 21, 2011 Geosyntec Geosynthetic Clay Liner 02772-9 SPECIFICATION NO: SECTION 02740

SPECIFICATION TITLE: GEOMEMBRANE LINER

PROJECT NO: 444853

PROJECT TITLE: ONONDAGA LAKE SCA FINAL DESIGN

CLIENT: HONEYWELL, INC.

					APPROVAL	.S
Issue	Date	Pages	Issue Description	Prepared	Checked	Approved
0	12Jul10	21	Original	JMS	RK	
1	13Oct10	20	Specification modified from an LLDPE geomembrane to a HDPE geomembrane	JMS	RK	JFB
2	21Apr11	20	 Response to Comments Page 8: ASTM D5397 added to table Page 19: ASTM D5397 added to Table 02740-1 and density requirement changed to minimum. Added statement to 3.05C. 	JMS	RK	JFB
Entire Specification Issued this Revision		tion sion	SPECIFICATION ISSUED FOR:			
Revised Pages Only Issued this Revision)nly sion	In-house Review Client Review/Ap Information Only	pproval D	Bid Construct Other	tion

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	2 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

SECTION 02740

GEOMEMBRANE LINER

PART 1 – GENERAL

1.01 SCOPE OF WORK

- A. The work covered in this Section consists of the installation of a 60-mil high density polyethylene (HDPE) geomembrane (textured on both sides). These geomembranes shall be placed in accordance with the Project Specifications and Drawings. The Contractor shall furnish all labor, materials, equipment, supervision, and incidentals necessary to perform the scope of work.
- B. All geomembrane material placed as a part of this project shall be placed, tested, and documented in accordance with this Section unless specifically approved by the Engineer.

1.02 RELATED WORK

- A. Work in this section includes, but is not limited to:
 - 1. Section 01030 Environmental Protection
 - 2. Section 01300 Submittal Procedures
 - 3. Section 01620 Health and Safety Requirements
 - 4. Section 02250 Low Permeability Soil Layer
 - 5. Section 02710 Geotextile Cushion
 - 6. Section 02772 Geosynthetic Clay Liner

1.03 REFERENCES

- A. Latest version of the American Society for Testing and Materials (ASTM) standards:
 - 1. ASTM D 792 Standard Test Methods for Density and Specific Gravity (Relative Density) of Plastics by Displacement.
 - 2. ASTM D 1004 Standard Test Method of Tear Resistance (Graves Tear) of Plastic Film and Sheeting.
 - 3. ASTM D 1238 Standard Test Method for Melt Flow Rates of Thermoplastics by Extrusion Plastometer.
 - 4. ASTM D 1505 Standard Test Methods for Density of Plastics by the Density-Gradient Technique.
 - 5. ASTM D 1603 Standard Test Method for Carbon Black Content in Olefin Plastics.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	3 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

6.	ASTM D 3895	Standard Test Method for Oxidative-Induction Time of
7		Polyoletins by Differential Scanning Calorimetry
7.	ASTM D 4218	Standard Test Method for Determination of Carbon
		Black Content in Polyethylene Compounds by the
		Muffle-Furnace Technique
8.	ASTM D 4833	Standard Test Method for Index Puncture Resistance of
		Geomembranes and Related Products.
9.	ASTM D 5321	Standard Test Method for Determining the Coefficient
		of Soil and Geosynthetic or Geosynthetic and
		Geosynthetic Friction by the Direct Shear Method.
10.	ASTM D 5397	Standard Test Method for Evaluation of Stress Crack
		Resistance of Polyolefin Geomembranes Using
		Notched Constant Tensile Load Test.
11.	ASTM D 5596	Standard Test Method for Microscopic Examination the
		Dispersion of Carbon Black in Polyolefin
		Geosynthetics.
12.	ASTM D 5994	Standard Test Method for Measuring the Core
		Thickness of Textured Geomembrane.
13.	ASTM D 6392	Standard Test Method for Determining the Integrity of
		Nonreinforced Geomembrane Seams Produced Using
		Thermo-Fusion Methods.
14.	ASTM D 6693	Standard Test Method for Determining Tensile
		Properties of Nonreinforced Polyethylene and
		Nonreinforced Flexible Polypropylene Geomembranes.
15.	ASTM D 7466	Standard Test Method for Measuring the Asperity
-0.		Height of Textured Geomembrane
16.	GRI GM 9	Cold Weather Seaming of Geomembranes.
10.		cond in caller bounding of coolinementation

1.04 SUBMITTALS

- A. Submit the following information to the Engineer for review not less than 45 calendar days prior to use for all geomembrane furnished.
 - 1. Geomembrane manufacturer capabilities, including daily production capacity available for this contract and manufacturing quality control procedures.
 - 2. A list of 10 completed facilities for which the Manufacturer has manufactured a minimum total of 10,000,000 square feet of polyethylene geomembrane. Provide the following information for each facility:
 - a. Name, location, purpose of facility, and date of installation;
 - b. Names of owner, project manager, design engineer, and installer; and
 - c. Thickness and surface area of geomembrane provided.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	4 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

- 3. Origin (resin supplier's name, resin production plant) and identification (brand name, number) of the polyethylene resin used.
- 4. Certification of minimum average roll values (95 percent lower confidence limit) for physical, mechanical, and environmental properties and the corresponding test procedures for the geomembrane properties listed in Table 1 for the 60-mil base liner geomembrane. Submit values that are specific to the resin used in manufacturing of the geomembrane.
- 5. Certification that HDPE welding rod is compatible with the specifications and consists of the same resin as the geomembrane.
- 6. Manufacturer warranty as specified in this Section.
- B. Submit to the Engineer for review not less than 14 calendar days prior to geomembrane use the following documentation on the resin used to manufacture any geomembranes:
 - 1. Copies of quality control certificates issued by the resin supplier including the production dates and origin of the resin used to manufacture the geomembrane for this Contract.
 - 2. Results of tests conducted by the Manufacturer to verify the quality of the resin used to manufacture the geomembrane rolls assigned to the project.
 - 3. Certification that no reclaimed polymer is added to the resin during the manufacturing of the geomembrane to be used for this project except as allowed by this specification.
- C. Submit to the Engineer for review the following documentation on geomembrane roll production at least 5 calendar days prior to transporting any geomembrane to the site.
 - 1. Manufacturing certificates for each shift's production of geomembrane, signed by the Manufacturer quality control manager, and notarized.
 - 2. Certificate shall include roll numbers and identification, sampling procedures and results of Manufacturer quality control tests, including descriptions of the test methods used (the Manufacturer quality control tests to be performed are given in Part 2 of this Section).
 - 3. Cold weather seaming procedures (including manufacturer specifications), which should follow the standards of GRI GM 9.
- D. Submit to the Engineer for review the following information from the Installer at least 14 calendar days prior to mobilization of the Installer to the site.
 - 1. Layout drawings showing the installation layout identifying geomembrane panel configurations, dimensions, details, locations of seams, as well as any variance or additional details which deviate from the Construction Drawings. The layout drawings shall be adequate for use as a construction

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	5 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

plan and shall include dimensions, details, etc. The layout drawings, as modified and/or approved by the Engineer, shall become part of the contract.

- 2. Installation schedule.
- 3. Copy of Installer's letter of approval or license by the Manufacturer.
- 4. Installation capabilities, including information on equipment proposed for this project, average daily production anticipated for this project and quality control procedures to include quality control organization.
- 5. A list of 10 completed facilities for which the Installer has installed a minimum of 5,000,000 square feet of polyethylene geomembrane. The following information shall be provided for each facility:
 - a. Name and purpose of the facility, its location, and installation dates.
 - b. Names of owner, project manager, and geomembrane manufacturer.
 - c. Name and qualifications of the supervisor of the installation crew;
 - d. Thickness and surface area of installed geomembrane;
 - e. Type of seaming and type of seaming apparatus used; and
 - f. Duration of installation.
- 6. Resumes of the Installer Superintendent and quality control chief to be assigned to this project, including dates and duration of employment.
- 7. Resumes of all personnel who will perform seaming operations on this project, including dates and duration of employment.
- 8. Evidence that the installation crew has the following experience.
 - a. The foreman shall have supervised the installation of a minimum of 50 acres of comparable geosynthetic systems, on a minimum of 5 different projects.
 - b. At least one seamer shall have experience seaming a minimum of 500,000 square feet of polyethylene geomembrane using the same type of seaming apparatus to be used at this site. Seamers with such experience will be designated "master seamers" and shall provide direct supervision over less experienced seamers.
 - c. All other seaming personnel shall have seamed at least 100,000 square feet of polyethylene geomembrane using the same type of seaming apparatus to be used at this site. Personnel who have seamed less than 100,000 square feet of seams shall be allowed to seam only under the direct supervision of the master seamer or Superintendent.
- E. Submit to the Engineer for review at least 14 days prior to geomembrane placement, a Certificate of Calibration less than 12 months old for the field tensiometer. Tensiometer shall be calibrated within one year of date of test. Calibration shall be traceable to national or industry recognized standards where possible.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	6 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

- F. Submit subgrade acceptance certificates, signed by the Installer, for each area to be covered by the geomembrane prior to that area being covered by geomembrane.
- G. Within 14 calendar days of completion of the geomembrane installation, submit a one-year installation warranty to the Engineer.

1.05 AS-BUILT DOCUMENTATION

- A. The Contractor shall submit as-built revisions to the Project Drawings in accordance with Section –01300 Submittal Procedures.
- B. In addition to preparation of as-built revisions to the Project Drawings, the Contractor shall provide as-built documentation for the placed geomembrane.

1.06 CONSTRUCTION QUALITY ASSURANCE

- A. The construction of the geomembrane will be monitored as required in the CQA Plan.
- B. The Engineer will perform material conformance testing of geomembrane materials and installation quality assurance testing of the geomembrane seams, as required in the CQA Plan.
- C. The Contractor shall be aware of the activities required of the Engineer by the CQA Plan and shall account for these activities in the construction schedule.
- D. The Contractor shall correct all deficiencies and nonconformances identified by the Engineer at no additional cost. The Contractor shall also provide assistance as needed to the post-construction electrical leak location survey to be performed for the base liner by a specialty leak location contractor reporting to the CQA Engineer. The work may include but not limited to: providing electrical isolation around perimeter and or liner penetrations; exposing the liner manually to create and repair test hole through the geomembrane; providing access to AC power; providing laborers to layout out survey grid; adding of water to soils (above and below liner) to promote electrical conductivity; installing electrical probes and wires under the liner; and assisting in the repair of any identified leaks.

PART 2 – PRODUCTS

2.01 RESIN

A. Provide geomembrane manufactured from new, first-quality polyethylene resin. Do not add reclaimed polymer to the resin. The use of polymer recycled during

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	7 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

the manufacturing process is permitted if performed with appropriate cleanliness and if the recycled polymer during the manufacturing process does not exceed 10 percent by weight of the total polymer weight. The percentage of recycled polymer shall not affect the quality of the finished product.

- B. Use high density polyethylene (HDPE) resin having the following properties:
 - 1. Formulated Sheet Density: 0.940 g/ml maximum (ASTM D792 Method A or ASTM D1505)
 - 2. Resin Specific Gravity: 0.93 g/ml minimum (ASTM D792 Method B or ASTM D1505).
 - 3. Melt Flow Index: 1.0 g/10 min., maximum (ASTM D1238 Condition E)

2.02 GEOMEMBRANE PROPERTIES

- A. The Contractor shall furnish HDPE geomembrane having properties that comply with the required values shown in Table 1 for 60-mil HDPE geomembrane.
- B. The 60-mil HDPE liner geomembrane material shall meet the minimum required peak and residual internal/interface friction angles shown in Section 02250: Low Permeability Soil Layer when tested as a layered sandwich representing the base liner system of the SCA (low permeability soil, geomembrane, geotextile cushion and gravel drainage layer) in accordance with ASTM D 5321. This test shall be performed at the frequency specified in Section 02250.
- D. In addition, furnish geomembrane that:
 - 1. contains a maximum of 1 percent by weight of additives, fillers, or extenders not including carbon black;
 - 2. does not have striations, pinholes, bubbles, blisters, nodules, undispersed raw materials, or any sign of contamination by foreign matter on the surface or in the interior;
 - 3. is free of holes, blisters, modules, undispersed raw materials, or any sign of contamination by foreign matter; and
 - 4. is manufactured in a single layer (thinner layers shall not be welded together to produce the final required thickness).

2.03 MANUFACTURING QUALITY CONTROL

- A. Resin:
 - 1. Sample and test resin at a minimum frequency of one test per rail car to demonstrate that the resin complies with the requirements of this Section.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	8 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

Perform tests on resin after the addition of additives to the virgin resin. Certify in writing that the resin meets the requirements of this Section.

2. Do not use any noncomplying resin.

B. Rolls:

- 1. Continuously monitor for geomembrane defects during manufacturing.
- 2. Do not supply geomembrane that exhibits any defects.
- 3. Regularly monitor for geomembrane thickness during manufacturing.
- 4. Do not supply geomembrane that fails to meet the specified thickness.
- 5. Sample and test the geomembrane, to demonstrate that its properties conform to the values specified in Table 1. Perform the following quality control tests at a minimum frequency, as shown:

Test	Procedure	Frequency
Thickness	ASTM D 5994	one per 50,000 ft^2
tensile strength	ASTM D 6693	one per 50,000 ft^2
tensile elongation	ASTM D 6693	one per 50,000 ft^2
tear resistance	ASTM D 1004	one per 50,000 ft^2
carbon black content	ASTM D 1603	one per 50,000 ft^2
carbon black dispersion	ASTM D 5596	one per 50,000 ft^2
specific gravity	ASTM D 1505	one per 50,000 ft^2
asperity height	ASTM D 7466	one per 50,000 ft^2
oxidative induction time	ASTM D 3895	one per formulation
Stress Crack Resistance	ASTM D 5397	one per formulation ^[1]

^[1]ASTM D 5397 is not appropriate for use on textured geomembranes. The test should instead be conducted on smooth edges of the textured geomembrane rolls or on smooth sheets made from the same formulation as being used for the textured geomembrane.

- 6. Provide a geomembrane sample for use in sandwich shear testing (ASTM D 5321) to demonstrate that the geomembrane properties conform to the shear strength parameters specified in Table 1.
- 7. If a geomembrane sample fails to meet the quality control requirements of this Section, sample and test rolls manufactured, in the same resin batch, or at the same time, as the failing roll. Continue to sample and test the rolls until the extent of the failing rolls are bracketed by passing rolls. Do not supply any failing rolls.
- C. Permit the Engineer to visit the manufacturing plant for project specific visits. If possible, such visits will be prior to, or during, the manufacturing of the geomembrane rolls for this project.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	9 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

2.04 LABELING

- A. Label the geomembrane rolls with the following information.
 - 1. thickness of the material;
 - 2. length and width of the roll;
 - 3. name of Manufacturer;
 - 4. product identification;
 - 5. lot number; and
 - 6. roll number.
- B. Geomembrane rolls not labeled in accordance with this Section or on which labels are illegible will be rejected and replaced.

2.05 TRANSPORTATION, HANDLING, AND STORAGE

- A. Deliver geomembranes to the site at least 14 calendar days prior to the planned deployment date to allow the Engineer adequate time to perform conformance testing on the geomembrane samples as described in the CQA Plan.
- B. Provide proper handling and storage of the geomembrane at the site. Protect the geomembrane from excessive heat or cold, dirt, puncture, cutting, or other damaging or deleterious conditions. Provide any additional storage procedures required by the Manufacturer.
- C. Store geomembrane rolls on palates or other elevated structures. Do not store geomembrane rolls directly on the ground surface. Do not store more than 3 rolls high.

PART 3 – EXECUTION

3.01 FAMILIARIZATION

- A. Prior to implementing any of the work described in this Section, the Contractor shall become thoroughly familiar with all portions of the work falling within this Section.
- B. Inspection:
 - 1. Prior to implementing any of the work in this Section, the Contractor shall carefully inspect the installed work of all other Sections and verify that all work is complete to the point where the installation of this section may properly commence without adverse impact.
 - 2. If the Contractor has any concerns regarding the installed work of other Sections, the Contractor shall immediately notify the Engineer in writing.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	10 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

Failure to inform the Engineer in writing or continuance of installation of the geomembrane will be construed as the Contractor's acceptance of the related work of all other Sections.

3.02 SUBGRADE SURFACE PREPARATION

- A. The Contractor shall provide certification in writing from the Geomembrane Installer that the surface on which the geomembrane will be installed is acceptable. This certification of acceptance shall be given to the Engineer prior to commencement of geomembrane installation in the area under consideration.
- B. Special care shall be taken to maintain the prepared soil surface.
- C. No geomembrane shall be placed onto an area which has been softened by precipitation or which has excessively cracked due to desiccation. The soil surface shall be observed daily to evaluate the effects of desiccation cracking and/or softening on the integrity of the subgrade.
- D. Any damage to the subgrade caused by installation activities shall be repaired at the Contractor's expense.

3.03 GEOMEMBRANE DEPLOYMENT

- A. General:
 - 1. The Contractor shall produce layout drawings prior to geomembrane deployment. These drawings shall indicate the geomembrane configuration, dimensions, details, locations of seams, etc. The layout drawings must be approved by the Engineer prior to the installation of any geomembranes. The layout drawings, as modified and/or approved by the Engineer, shall become part of these specifications.
 - 2. Do not deploy geomembrane until the layout drawings are approved by the Engineer.
 - 3. Do not deploy a geomembrane panel in an area until the Engineer has been provided with a certificate of subgrade acceptance for that area.
 - 4. Do not deploy geomembranes until Engineer completes conformance evaluation of the geomembrane and performance evaluation of previous work, including evaluation of Contractor's survey results for previous work.
 - 5. Deploy each geomembrane panel in accordance with the approved layout drawings.
- B. Field Panel Identification:

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	11 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

- 2. Give each field panel an identification code (number or letter-number). This identification code shall be agreed upon by the Engineer and the Installer.
- C. Field Panel Placement:
 - 1. Place each geomembrane panel one at a time and seam each panel immediately after its placement.
 - 2. Use temporary rubsheets as required to prevent displacement or damage to underlying geosynthetics. High spots in geomembrane-backed geosynthetic clay liners shall be covered by a temporary rubsheets during placement of geomembrane.
 - 3. Do not place geomembrane panels when the ambient temperature is below 40° Fahrenheit (F), unless authorized in writing by the Engineer. For cold weather (<40°F) deployment, use the additional procedures authorized in writing by the Engineer. Additional procedures authorized by the engineer for cold weather seaming shall include, more trial welds, deploying panels the night before to maintain consistent temperatures between the panels being seamed, and utilizing temporary enclosed structures with heaters. In addition, all manufacturer specifications for cold weather seaming and panel placement for the selected geomembrane shall be followed. The procedures will also address placement of the gravel during cold weather. The manufacturer recommendations for cold weather will be followed.
 - 4. Do not place geomembranes during any precipitation, in the presence of heavy fog or dew, in an area of ponded water, or in the presence of wind in excess of 20 miles per hour.
 - 5. Ensure that:
 - a. No vehicular traffic drives directly on the geomembrane.
 - b. Equipment used does not damage the geomembrane by handling, trafficking, or leakage of hydrocarbons (i.e., fuels).
 - c. Personnel working on the geomembrane do not smoke, bring glass onto the geomembrane, or engage in other activities that could damage the geomembrane.
 - d. The method used to unroll the panels does not scratch or crimp the geomembrane and does not damage lower geosynthetics or the supporting soil.
 - e. The method used to place the panels minimizes wrinkles (especially differential wrinkles between adjacent panels). The method used to place the panels results in intimate contact with geosynthetic clay liner, where present. Adjust or repair any area of geomembrane wrinkles where the wrinkle height causes a concern for wrinkle to fold over during placement of material on top. A wrinkle height of 4 inches

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	12 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

measured perpendicular to the slope can be used as a general guide. The method used to place the panels does not cause the panels to lift up or trampoline during the coolest portion of the day.

- g. The geomembrane is anchored or weighted with sandbags, or the equivalent, to prevent damage or uplift from wind. Install sufficient anchoring or weighting to prevent uplift and maintain such system until overlying material is placed.
- 6. Replace any field panel or portion thereof that becomes damaged (torn, twisted, or crimped). Remove from the work area damaged panels or portions of damaged panels.

3.04 FIELD SEAMING

- A. Personnel shall be experienced as specified in this Section. Do not perform seaming unless a "master seamer" and the Engineer are on-site.
- B. Orient seams parallel to the line of maximum slope (i.e., oriented down, not across, the slope). Minimize the number of seams in corners and at odd-shaped geometric locations. No horizontal seam shall be less than 10 feet from the toe of the slope, except where approved by the Engineer. Do not locate seams at an area of potential stress concentration.
- C. Weather Conditions for Seaming:
 - 1. Do not seam geomembrane at ambient temperatures below 40°F or above 104°F, unless authorized in writing by the Engineer. Do not seam geomembrane at sheet temperatures above 158°F. For cold (<40°F) or hot (>104°F) weather seaming, use the additional procedures authorized in writing by the Engineer. Cold weather procedures (including manufacturer specifications) will be a contractor submittal that will be made available to the regulators.
 - 2. Measure ambient temperatures between 0 to 6 inches above the geomembrane surface.
 - 3. In all cases the geomembrane seam areas shall be dry and protected from wind. Do not seam geomembrane during periods of precipitation or if winds are in excess of 20 miles per hour.
- D. Overlapping and Temporary Bonding:

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	13 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

- 1. Sufficiently overlap geomembrane panels for welding and to allow peel tests to be performed on the seam. Any seams that cannot be destructively tested because of insufficient overlap are failing seams.
- 2. Control the temperature of the air at the nozzle of heat bonding apparatus such that the geomembrane is not damaged.
- E. Seam Preparation:
 - 1. Prior to seaming, clean the seam area and ensure that area to be bonded is free of moisture, dust, dirt, debris of any kind, and foreign material.
 - 2. If seam overlap grinding is required, complete the process according to the Manufacturer's instructions or within 60 minutes of the seaming operation. Do not grind to a depth that exceeds ten percent of the geomembrane thickness. Grinding marks shall not appear beyond 0.25 inch of the extrudate after it is placed.
 - 3. Align seams with the fewest possible number of wrinkles and "fishmouths".
- F. General Seaming Requirements:
 - 1. Extend seams to the outside edge of panels to be placed in the anchor trench.
 - 2. If required, place a firm substrate such as a flat board or similar hard surface directly under the seam overlap to achieve proper support.
 - 3. Cut fishmouths or wrinkles at the seam overlaps along the ridge of the wrinkle to achieve a flat overlap. Seam the cut fishmouths or wrinkles and patch any portion where the overlap is less than 6 inches with an oval or round patch of geomembrane that extends a minimum of 6 inches beyond the cut in all directions.
 - 4. Place the electric generator used for power supply to the welding machines outside the area to be lined or mount it on soft tires such that no damage occurs to the geomembrane. Properly ground the electric generator. Place a smooth insulating plate or fabric beneath the hot welding apparatus after use.
- G. Seaming Process:
 - 1. Approved processes for field seaming are extrusion welding and fusion welding. The primary method of welding shall be fusion. Seaming equipment shall not damage the geomembrane. Use only geomembrane Manufacturer-approved equipment.
 - 2. Extrusion Equipment and Procedures:
 - a. Maintain at least one spare operable seaming apparatus on site.
| Project No. Title: | 444853 Onondaga Lake SCA Final Design | Revision: | 2 |
|---------------------|---------------------------------------|-----------|-------------|
| Specification No. | Section 02740 | Page: | 14 of 21 |
| Specification Title | Geomembrane Liner | Date: | 21 April 11 |

- b. Equip extrusion welding apparatus with gauges giving the temperature in the apparatus and at the nozzle.
- c. Prior to beginning a seam, purge the extruder until all heat-degraded extrudate has been removed from the barrel. Whenever the extruder is stopped, purge the barrel of all heat-degraded extrudate.
- 3. Fusion Equipment and Procedures:
 - a. Maintain at least one spare operable seaming apparatus on site.
 - b. Fusion-welding apparatus shall be automated self-propelled devices equipped with gauges giving the applicable temperatures and pressures.
 - c. Fusion-welding apparatus shall produce a double-track seam.
 - d. Abrade the edges of cross seams to a smooth incline (top and bottom) prior to extrusion welding.
- H. Trial Seams:
 - 1. Make trial seams on excess pieces of geomembrane to verify that seaming conditions are adequate. Conduct trial seams on the same material to be installed and under similar field conditions as production seams. Conduct trial seaming at the beginning of each seaming period, after every four hours of continuous seaming, every time seaming equipment is changed and if significant changes in geomembrane temperature are observed, for each seaming apparatus used that day prior to seaming. In addition, each seamer shall make at least one trial seam each day, for each day that seaming is performed by that seamer. Conduct trial seaming under the same conditions as the actual seaming. Prepare trial seams that are at least 15 feet long by 1 foot wide (after seaming) with the seam centered lengthwise for fusion equipment and at least 3 feet long by 1 foot wide for extrusion equipment. Prepare seam overlap as indicated in the "Overlapping and Temporary Bonding" Article of this Part.
 - 2. Cut four specimens, each 1.0 inch wide, from the trial seam sample. Test two specimens in shear and two in peel, using a field tensiometer. The test specimens shall not fail in the seam. If a specimen fails, repeat the entire operation. If the additional specimen fails, do not accept the seaming apparatus or seamer until the deficiencies are corrected and two consecutive successful trial seams are achieved. A seamer may start production seaming prior to testing of the trial seams. In the event the trial seam fails, all production seams by the seamer are failed seams.
- I. Nondestructive Seam Continuity Testing:
 - 1. Nondestructively test for continuity field seams over their full length. Perform continuity testing as the seaming work progresses, not at the

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	15 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

completion of field seaming. Record the location, date, unit number of test apparatus, name of tester and results of testing. Complete any required repairs in accordance with the "Defects and Repairs" Article of this Part. Apply the following procedures:

- a. use vacuum testing for extrusion welds; and
- b. use air pressure testing for double-track fusion seams.
- 2. Vacuum Testing:
 - a. Use the following equipment:
 - i. A vacuum box assembly consisting of a stiff housing, a transparent viewing window, a soft neoprene gasket attached to the bottom, port hole or valve assembly, and a vacuum gauge.
 - ii. A system for applying 5 pound per square inch (psi) gauge suction to the box.
 - iii. A bucket of soapy solution and applicator.
 - b. Follow these procedures:
 - i. Energize the vacuum pump and reduce the tank pressure to 5 ± 1 psi gauge.
 - ii. Wet an area of the geomembrane seam larger than the vacuum box with the soapy solution.
 - iii. Place the box over the wetted area.
 - iv. Close the bleed valve and open the vacuum valve.
 - v. Ensure that a leak tight seal is created.
 - vi. Examine the geomembrane through the viewing window for the presence of soap bubbles for not less than 20 seconds.
 - vii. If no bubbles appear after 20 seconds, close the vacuum valve and open the bleed valve, move the box over the next adjoining area with a minimum 3 inch overlap, and repeat the process.
 - viii. Mark all areas where soap bubbles appear with a marker that will not damage the geomembrane and repair in accordance with the "Defects and Repairs" Article of this Part.
- 3. Air Pressure Testing:
 - a. Use the following equipment:
 - i. an air pump (manual or motor driven) or air reservoir, equipped with a pressure gauge, capable of generating and sustaining a pressure between 25 and 30 pounds per square inch;
 - ii. a rubber hose with fittings and connections; and
 - iii. a hollow needle, or other approved pressure feed device.
 - b. Follow these procedures:
 - i. Seal both ends of the seam to be tested.

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	16 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

- ii. Insert needle, or other approved pressure feed device, into the tunnel created by the fusion weld.
- iii. Insert a protective cushion between the air pump and the geomembrane.
- iv. Energize the air pump to a pressure between 25 and 30 pounds per square inches, close valve, and sustain the pressure for not less than 5 minutes.
- v. If loss of pressure exceeds 3 pounds per square inches, or does not stabilize, locate faulty area and repair in accordance with the "Defects and Repairs" Article of this Part.
- vi. Cut opposite end of air channel from pressure gauge and observe release of pressure to ensure air channel is not blocked.
- vii. Remove needle, or other approved pressure feed device, and seal both ends in accordance with the "Defects and Repairs" Article of this Part.
- J. Destructive Testing:
 - 1. Destructive testing shall be performed by the CQA Personnel. The Contractor shall provide assistance if requested by the CQA Personnel to obtain samples. Perform destructive seam tests to evaluate seam strength and integrity (see Table 2 for seam properties of 60-mil HDPE). Perform destructive testing as the seaming work progresses, not at the completion of field seaming.
 - 2. Sampling and Testing:
 - a. Collect destructive test samples at a minimum average frequency of one test location per 500 feet of seam length and at additional locations of suspected nonperformance. A minimum of one test sample for each seaming machine operating on a given day is required. The Engineer will select test locations, including locations with evidence of excess geomembrane crystallinity, contamination, offset seams, or any other evidence of inadequate seaming.
 - b. Cut samples at the locations designated by the Engineer at the time the locations are designated. Number each sample and identify the sample number and location on the panel layout drawing. Immediately repair all holes in the geomembrane resulting from the destructive seam sampling in accordance with the repair procedures described in the "Defects and Repairs" Article of this Part. Test the continuity of the new seams in the repaired areas according to "Nondestructive Seam Continuity Testing" Article of this Part.
 - c. Cut two strips 1 inch wide and 12 inch long with the seam centered parallel to the width from either side of the sample location. Test the two 1-inch wide strips in the field tensiometer in the peel mode. The

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	17 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

Engineer may request an additional test in the shear mode. If these samples pass the field test, prepare a laboratory sample at least 1 foot wide by 3.5 feet long with the seam centered lengthwise. Cut the laboratory sample into three parts and distribute as follows:

- i. one portion 1 foot long to the Installer;
- ii. one portion 1.5 feet long to the Engineer for testing; and
- iii. one portion 1 foot long to the Engineer for archival storage.
- 3. In the event of failing field or laboratory test results, the Contractor may reconstruct the entire seam between two passing destructive tests; otherwise, the Engineer will identify the extent of the nonconforming area following the procedures given in the CQA Plan. Obtain additional samples for testing as requested by the Engineer.
- K. Defects and Repairs:
 - 1. Inspect the geomembrane before and after seaming for evidence of defects, holes, blisters, undispersed raw materials, and any sign of contamination by foreign matter. The surface of the geomembrane shall be clean at the time of inspection. Sweep or wash the geomembrane surface if surface contamination inhibits inspection.
 - 2. Test each suspect location, both in seam and non-seam areas, using the methods described in the "Nondestructive Seam Continuity Testing" Article of this Part. Repair each location that fails nondestructive testing.
 - 3. Cut and reseam wrinkles not conforming with Part 2 of this Section. Test the seams thus produced like any other seam.
 - 4. Repair Procedures:
 - a. Repair any portion of the geomembrane exhibiting a flaw, or failing a destructive or nondestructive test. Use the most appropriate of the available procedures:
 - i. patching, used to repair large holes, tears, undispersed raw materials, and contamination by foreign matter;
 - ii. abrading and reseaming, used to repair small sections of extruded seams;
 - iii. spot seaming, used to repair minor, localized flaws;
 - iv. capping, used to repair long lengths of failed seams;
 - v. topping, used to repair areas of inadequate seams, which have an exposed edge less than 4 inches in length; and
 - vi. removing bad seam and replacing with a strip of new material seamed into place (used with long lengths of fusion seams).
 - b. When making repairs, satisfy the following:

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	18 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

- i. abrade surfaces of the geomembrane that are to be repaired no more than 20 minutes prior to the repair;
- ii. clean and dry all geomembrane surfaces immediately prior to repair;
- iii. only use approved seaming equipment; and
- iv. extend patches or caps at least 6 inches beyond the edge of the defect, and round corners of patches to a radius of at least 3 inches.
- 5. Repair Verification:
 - a. Test each repair using the methods described in the "Nondestructive Seam Continuity Testing" Article of this Part. Repairs that pass the nondestructive test are adequate unless the Engineer elects to also perform destructive tests. Re-repair and retest failed tests.

3.05 MATERIALS IN CONTACT WITH THE GEOMEMBRANE

- A. Take all necessary precautions to prevent damage to the geomembrane during the installation of other components of the liner system.
- B. Do not drive equipment directly on the geomembrane. Only use low ground pressure equipment above the geomembrane.
- C. The protection measures for the liner along the perimeter channel area include, restricting traffic to foot traffic and low weight portable equipment and tools on an as-needed basis, performing routine visual inspections, and repairing the liner. At the start of every dredge season, the exposed liner will be inspected. Repairs will be performed as necessary based on the inspection.

3.06 SURVEY CONTROL

- A. Survey the installed geomembrane for preparing the as-built panel layout drawing.
- B. Locate panel seams and intersections as requested by the Engineer.

3.07 GEOMEMBRANE ACCEPTANCE

- A. The Contractor shall retain all ownership and responsibility for the geomembrane until accepted by the Engineer.
- B. The geomembrane shall be accepted by the Owner when:
 - 1. The installation is finished;

Project No. Title:	444853 Onondaga Lake SCA Final Design	Revision:	2
Specification No.	Section 02740	Page:	19 of 21
Specification Title	Geomembrane Liner	Date:	21 April 11

- 2. All documentation of installation is completed including the Engineer's final report; and
- 3. Verification of the adequacy of all field seams and repairs, including associated testing, is complete.

3.08 **PROTECTION OF WORK**

- A. The Contractor shall protect all prior work and all materials and completed work of other Sections.
- B. In the event of damage, the Contractor shall make all repairs or replacements necessary to be in full compliance with the Contract Documents.

TABLE 1REQUIRED GEOMEMBRANE PROPERTIES FOR 60-MIL HDPE

Properties	Qualifiers	Units ⁽¹⁾	Specified Values	Test Method
Physical Properties				
Thickness	minimum average	Mils	60	ASTM D 5994
Asperity Height (Note 3)	minimum average	Mils	10	ASTM D 7466
Density	minimum	g/cm ³	0.940	ASTM D 1505
Carbon Black Content	range	%	2.0-3.0	ASTM D 1603
Carbon Black Dispersion	N/A	None	9 of 10 views in category 1 or 2	ASTM D 5596
Tensile Properties (each direction)				
1. Tensile Strength (force per unit width at break)	minimum	lb/in	90	ASTM D 6693
2. Elongation at Break	minimum	%	100	ASTM D 6693
3. Tensile Strength (force per unit width at yield)	minimum	lb/in	126	ASTM D 6693
4. Elongation at Yield	minimum	%	12	ASTM D 6693
Tear Resistance	minimum	Lb	42	ASTM D 1004 Die C Puncture
Puncture Resistance	minimum	Lb	90	ASTM D 4833
Shear Strength	minimum		See Note 2	ASTM D 5321
Oxidative Induction Time (OIT)	minimum average	Minutes	100	ASTM D 3895
Stress Crack Resistance	minimum	Hours	300	ASTM D 5397 (Note 4)

Notes:

1. mils = milli-inches

% = percent

g = grams

 $g/cm^3 = grams$ per cubic centimeter

lb = pound

lb/in = pounds per inch

- 2. The required peak and residual shear strength parameters are included in a figure as part of Section 02250.
- 3. Of 10 readings, 8 out of 10 must be greater or equal to 7 mils and the lowest must be greater or equal to 5 mils.
- 4. ASTM D 5397 is not appropriate for use on textured geomembranes. The test should instead be conducted on smooth edges of the textured geomembrane rolls or on smooth sheets made from the same formulation as being used for the textured geomembrane.

Properties	Qualifiers	Units ⁽³⁾	Specified Values	Test Method
Shear Strength ⁽¹⁾				
Fusion	minimum	lb/in	120	ASTM D 6392
Extrusion	minimum	lb/in	120	ASTM D 6392
Peel Adhesion			FTB ⁽²⁾	
Fusion	minimum	lb/in	91	ASTM D 6392
Extrusion	minimum	lb/in	78	ASTM D 6392

TABLE 2REQUIRED GEOMEMBRANE SEAM PROPERTIES FOR 60-MIL HDPE

Notes:

- 1. Also called "Bonded Seam Strength".
- 2. FTB = Film Tear Bond. (Maximum 10 percent seam separation)
- 3. lb/in = pounds per inch

[END OF SECTION]